

THESIS REPORT  
ON  
**5 STAR HOTEL IN  
LUCKNOW, UTTAR PRADESH**

A THESIS SUBMITTED  
IN PARTIAL FULFILLMENT OF THE REQUIREMENT FOR THE DEGREE OF:

**BACHELOR OF INTERIOR DESIGN**  
BY  
**RAJKANYA SINGH**  
**(ROLL. NO. 2200107002)**

**UNDER THE GUIDANCE OF**  
**PROF. KESHAV KUMAR**



TO THE  
**SCHOOL OF ARCHITECTURE AND PLANNING**  
**BABU BANARASI DAS UNIVERSITY,**  
**LUCKNOW.**

**SESSION - 2022-23**

## **CERTIFICATE**

I hereby recommend that the thesis entitled "**5 STAR HOTEL IN LUCKNOW, UTTAR PRADESH**", prepared by **RAJKANYA SINGH** under the supervision, is the bonfire work of the student and can be accepted as a partial fulfillment for the award of Bachelor's Degree in Interior Design, School of Architecture BBDU, Lucknow.

---

Prof. Keshav Kumar

(Thesis guide)

---

Prof. Mohit Kumar Agarwal

(Dean Dept. Of Architecture)

Recommendation: - Accepted

Not Accepted

---

External Examiner

---

External Examiner

## **ACKNOWLEDGEMENT**

Our hard work never shines if do not convey our heart feel gratitude to those people from whom we have got considerable support and encourage during this project.

To start with, First and foremost, gratitude towards almighty GOD for his blessings. Then I would like to thank all my faculty members who have supported and guided me all these memorable 4 years.

I would like to thank my thesis coordinator **AR. SHAILESH KUMAR YADAV** and **AR. VERSHA VERMA** who left no stone unturned to shape our thesis in the best possible way and also for his untimely help whenever required.

Furthermore, I would like to thank my thesis guide **PROF. KESHAV KUMAR** whose valuable guidance helped us to understand the project better at every stage. I am grateful for patiently examining my works. It has been a learning experience and motivating mission in the past few months due to their diligent supervision.

I would further like to show my gratitude to my family members, for giving full assistance whenever required and being there with me in all ups and downs. Their motivation and support helped me to be more dedicated and inclined towards my goal.

I would not forget to remember my friends and my senior ALOK KUMAR for their encouragement and more over for their timely support and guidance till the completion of my project work.

THANK YOU

RAJKANYA SINGH

Roll No.: - 2200107002

BBD UNIVERSITY, LUCKNOW.

**BABU BANARASI DAS UNIVERSITY, LUCKNOW  
(U.P.).**

**Certificate of thesis submission for evaluation**

1. Name : **RAJKANYA SINGH**
2. Roll No. : **2200107002**
3. Thesis Title : **5 STAR HOTEL IN LUCKNOW, UTTAR PRADESH**
4. Degree for which the thesis is submitted: **BACHELOR OF INTERIOR DESIGN**
5. Faculty of University to which the thesis is submitted: Yes /No
6. Thesis preparation guide was referred to for preparing the thesis. Yes/No
7. Specification regarding thesis format have been closely followed. Yes/No
8. The content of the thesis has been organized based on the guidelines. Yes /No
9. The thesis has been prepared without resorting to plagiarism Yes /No
10. All the sources used have been cited appropriately Yes /No
11. The thesis has not been submitted elsewhere for a degree. Yes/No
12. Submitted 3 hard bound copied plus one CD Yes/No

.....  
(Signature of the Guide)

**PROF. KESHAV KUMAR**

.....  
(Signature of the Candidate)

**RAJKANYA SINGH**  
Roll No:- 2200107002

## **DECLARATION**

I hereby declare that the work done in this thesis project is my own work and I have collected the data from various sources, which I have duly acknowledged in my report.

Date:-

Rajkanya Singh

Place: Lucknow

Roll No: 2200107002

Year : 2022-2023

Bachelors of Interior Design

BBD University Lucknow

# **BABU BANARASI DAS UNIVERSITY**

## **B.ID Thesis 2021-2022**

### **(Certificate)**

NAME OF STUDENT : RAJKANYA SINGH

Roll No: 2200107002

BRANCH: BACHELOR OF INTERIOR DESIGN

DEPARTMENT: SCHOOL OF ARCHITECTURE AND PLANNING

THESIS TITLE: 5 STAR HOTEL

THESIS GUIDE: PROF. KESHAV KUMAR

REMARKS: SATISFACTORY / NOT SATISFACTORY (IN CASE OF NOT SATISFACTORY GIVE COMMENTS):

---

---

---

(Sign Of Thesis Guide)

(Sign of External Examiner)

---

(Sign Of Thesis Coordinator)

(Sign of External Examiner )

---

(Sign Of H.O.D)

(Sign of Dean of Department)

## **TABLE OF CONTENT**

<b>TITLE</b>	<b>PAGE NO</b>
Certificate	2
Acknowledgement	3
Evaluation Certificate	4
Declaration	5
Abstract	8
CHAPTER 1: INTRODUCTION	9-21
CHAPTER 2: SITE ANALYSIS	22-55
CHAPTER 3: LITERATURE STUDY	56-105
CHAPTER 4: CASE STUDY	106-127
CHAPTER 5: CONCEPT	128-151
CHAPTER 6: STANDARDS	152-166
CHAPTER 7: BIBLOGRAPHY	167-168
CHAPTER 8: DESIGN DEVELOPMENTS	169-

## **ABSTRACT**

This thesis paper concerns about the formation of interior perceptions in 5 STAR HOTEL. The environment forms, basis of many behavioral traits.

The aim of the thesis project is to understand the technical function of a hotel complex. Its relationship of the surrounding with emphasis on exterior setting in conjunction with interior. Hotel provided regarding tourism, recreation, business etc.

A summary of the cognitive and emotional dimensions can lead to better understanding of the perception of a luxury hotel. This study confirms the idea that the perception of luxury value is influenced not only by the social purpose aussi by financial, functional and individual aspects. This study showed that the norms and standards of the hotels are not always synonymous with luxury. Therefore, an empirical study was done.

This study shows that customers in the hospitality sector have different perceptions of luxury of five star hotels and that the standards of stars is not enough to be used in measuring the luxury of hotels.

Planning a hotel we must balance functional, layout and aesthetic issues to develop a property that simultaneously meets the needs of the guests, the staff, and the owner. In general, Five Star properties have public areas that are heavily design oriented, with the function aspects carefully integrated to enhance, yet not dominate the space.

# **CHAPTER-01**

## **INTRODUCTION**

## **TOPIC 01 HOTEL**

### **INTRODUCTION:-**

- A hotel is an establishment that provides paid lodging on a short-term basis. Facilities provided inside a hotel room may range from a modest-quality mattress in a small room to large suites with bigger, higher-quality beds, a dresser, a refrigerator and other kitchen facilities, upholstered chairs, a flat screen television, and en-suite bathrooms.
- A hotel is defined by the British Law as a ‘place where bonafide travelers can receive food or shelter, provided he/she is in a position to pay for it and is in a fit condition to be received’. Hence, a hotel must provide food (and beverage) and lodging to a traveler on payment, but the hotel has the right to refuse if the traveler is not presentable (either drunk, or disorderly, or unkempt) or is not in a position to pay for the services.

### **STAR RATING OF A HOTEL:-**

- Star rating symbolize the level of service, rangeof facilities and quality of guest care.
- Hotel are required to meet progressively higher standards as they move up the scale from one to five Stars.
- **One-Star:** A one-star rating often means a property has no frills and only offers basic accommodations. A one-star rating doesn't necessarily mean a hotel is dirty, unkept or in a bad location. It simply means you'll have a place to sleep, and that's pretty much it.
- **Two-Star:** Like one-star hotels, two-star properties are typically more affordable than hotels. that have a higher rating — they are also usually quite comfortable.
- **Three-Star:** Three-star hotels ordinarily have some unique amenities and provide quality service.
- **Four-Star:** Four-star hotels are often noted for their upscale quality and extraordinary comfort.
- **Five-Star:** A five-star property
  - provides flawless guest services in a state-of-the-art facility. As a five-star property, such as premium dining options and personalized services to its guests. With no detail being overlooked, these hotels commonly even provides high-end, luxury toiletries for guests.

## **PROFESSIONAL CLASSIFICATION OF HOTEL INDUSTRY:-**

- In India the system depends on the number and standard of facilities , provided by the hotel. There is a statutory appointed committee known as **H.R.A.C.C. (HOTEL AND RESTAURANT APPROVAL AND CLASSIFICATION COMMITTEE)** which comprise of representatives of government and the Trade. The committee classifies hotel again and sets criteria of standards and award star rating .This criteria classifies the standards as necessary essential and desirable.” The Star rating range from 1 to 5 and 5 star rating is equivalent to first class hotels by norms.
- Hotel size: the number of rooms available.(Under 200 Rooms,200 to 399 rooms, 400 to 700 rooms and more than 700 rooms.
- Location: the geographic area or the proximity to certain attractions or facilities.
- Target markets: the type of guests that the hotel caters to, such as business travelers, leisure travelers, families, etc.
- Levels of service: the quality and range of services and amenities offered by the hotel, such as room service, concierge, spa, etc.
- Facilities provided: the features and facilities that the hotel has, such as restaurants, bars, swimming pools, conference rooms, etc.
- Ownership and Affiliations (Independent Hotels , Single Owner Hotels , Chain Hotel).
- Levels of Service (World Class Service ,Mid Range Service and Budget limited Service.

## **TYPES OF HOTEL:-**

### **Chain Hotel:**

Also known as a “branded hotel,” a chain hotel is affiliated with a brand that may have strict guidelines for amenities and design. Some chain hotels are part of a larger ownership group, while other chain hotels have independent owners but follow the same brand standards. Popular hotel chains are Courtyard, Holiday Inn, and Westin.



### **Independent Hotel:**

A hotel that is independently owned and operated with no brand standards or guidelines.




### **Boutique Hotel:**

A hotel that incorporates unique design and personalized service, often with a theme or local influences. Boutique hotels are usually small (under 100 rooms) and independently owned, though some boutique hotels are part of collections like Leading Hotels of the World or chains like the Curio Collection by Hilton.



## **Resort:**

A resort offers everything necessary for a vacation on-site, such as restaurants, bars, pools, spas, recreational facilities, kids clubs, and entertainment venues. Popular resort brands include Sandals and Four Seasons, though there are many independent resorts too.



### **Airport Hotel:**

An airport hotel is located near - you guessed it! - an airport. Airport hotels usually provide free airport transportation for a seamless transfer.



### **Conference Hotel:**

Catering to business travelers and groups, conference hotels have extensive function space, catering services, and event planners to suit trade shows, conventions, or other large events.



### **All-Suite Hotel:**

A hotel which contains only suite-style guestrooms, which are guestrooms that have separate sleeping and living areas. Embassy Suites is a popular all-suite hotel brand.

### **Motel:**

Short for a “motor hotel,” motels are often located next to a highway in rural areas and offer basic amenities at a low price.



## MY THEME FOR HOTEL:-

- **Biophilia** means love for nature incorporated in built environments with greenery and natural elements.
- Biophilic design elements enhance air quality, airflow, circadian rhythm, heart rate and ordinary human health.
- **Stephen kellert and Edward O. Wilson** (2000) the founder of biophilia Design.



MORE LIGHT AND AIR



DISPLAY NATURE



PIECE OF ART



INCORPORATE



NATURE



INCLUDE FIRE



INCLUDE WATER FEATURES



INCLUCATE MISMATCHED FURNITURE



GREEN ROOM SCHEMES



SHAPE



## **ELEMENTS OF BIOPHILIC THEME DESIGN:-**

Biophilic theme generated in **Singapore city**. Singapore city also known as **GARDEN CITY**.

- ENVIRONMENTAL FEATURES.
- NATURAL SHAPES AND FORMS.
- RESTORATIVE PATTERNS AND PROCESS.
- LIGHT AND SPACE.
- PLACE BASED RELATIONSHIPS.
- EVOLVED HUMAN NATURE RELATIONSHIPS.


## **BENEFITS OF BIOPHILIC DESIGN :-**

- It's important society reconnects to nature because it will be the only way to get ourselves out of this critical situation we have dug ourselves into. Climate change that is.
- The benefits of biophilic design are split into two sections. Benefits seen on an individual level and those seen on a larger scale or even a global scale. It's clear that incorporating nature into our lives has benefits, for us and nature, so now it's time to implement it. The whole world needs to adopt this type of design.



## **HISTORY \$ BACKGROUND:-**

The history of hotel is intimately connected to that of civilizations. Or rather, it is a part of that history. Facilities offering guest hospitality have been in evidence since early biblical times. The Greeks developed thermal baths in villages designed for rest and recuperation. Later, the Romans built mansions to provide accommodation for travelers on government business. The Romans were the first to develop thermal baths in England, Switzerland and the Middle East. Later still, caravanserais appeared providing a resting place for caravans along Middle Eastern routes. In the Middle Ages, monasteries and abbeys were the first establishments to offer refuge to travelers on a regular basis. Religious orders built inns, hospices and hospitals to cater for those on the move.



**A Middle-Age Caravanserai in the Middle East**



**19th Century Hotel in France**



**21st Century Hotel in Dubai**

## **NEED OF THE TOPIC:-**

Hospitalities is one of the biggest industries of the world. When it comes to hospitality interiors, business comes first commercial interior designers in the hospitality field of work in tandem with architect, contractors, and manufacturers to ensure all physical structures and archietectural element are aligned with client visison and business requirement Hotel, spas and other ventures have some most beautiful and luxurious interiors, an interior designer knows to create balance between high end luxury and top notch functionality to create spaces that both business owners and customers will love.

## **AIM AND OBJECTIVE:-**

To develop tourism industry as a whole inside and out-side the state and to develop national and international tourism in india and abroad necessasrry .

- To promote legislation calculated to benefits, improve and expand the hotel and tourist industries.
- The objective of interior design is to achieve beauty, expressiveness and functionalism.

### **BEAUTY:-**

Is not the only objective in planning and fur-nishing accommodation areas; in addition the areas should express an idea and most important of all, should function effectively.

### **EXPRESSIVENESS:-**

To express some theme: Could be naturalness, sophistication, formality, royalty, warmth, coolness, freshness, antiquity and so on.

### **FUNCTIONALISM:-**

Its spaces and furniture should serve the purpose for which they are intended.

- There should be optimum utilization of space.
- It should be easily maintainable.
- It should be convenient to the guests. It should be practical in cost and within the budget constraints as far as possible

### **FORM-**

Without the beauty of form good texture color or decoration can be of no use. However a particular chair is not well designed unless it accommodates itself to the human form The form of an object should thus suit its function.

## **TENTATIVE PROJECT REQUIREMENT:-**

### **REQUIREMENTS FOR THE LUXURY FIVE STAR HOTEL**

- Rooms and suits( standard,executive&luxury).
- Meeting and conference facilities.
- Banquet halls.
- Restaurants with well equipped kitchens.
- Library and reading room.
- Bars & discotheque.
- Offices for hotel staff.
- Services areas (cloak room, toilets, elevators, etc.).
- Facilities (beauty parlor, flower shop,moneyexchange,travel desk safetylockers,medicine shop).
- Outdoor swimming pool & heated swimming pool.
- Health, fitness & yoga centre.
- Laundry and dry-cleaning areas.
- Leisure and sports.
- Guest elevators separate from staff elevators.
- Luggage storage in which bags are out of guest view.
- Multilingual Staff.
- Residences for hotel staff.
- Dormitories for drivers.
- Store rooms.
- Service rooms.
- Disabled facilities.



**THEME BASED HOTEL  
PEARL PALACE HERITAGE JAIPUR**

## **METHODOLOGY:-**

- UNDERSTANDING THE BASIC NEED OF DESIGN SCOPE LIMITATIONS STUDIES.
- STUDIES RELATED TO THE PROJECT.
- SITE ANALYSIS.
- STUDY OF SITE CONDITIONS AND EXISTING FEATURES.
- SITE SURROUNDING STUDIES.
- SITE CLIMATE STUDIES.
- CASE STUDIES.
- LITERATURE STUDIES.
- LIBRARY STUDIES.
- ANALYZING THE COLLECTED DATA.
- FINALIZING THE AREA REQUIREMENT ON THE BASIS OF ANALYSIS.
- AREA ANALYSIS.
- CONCEPT AND THEME SHEET.
- CASE STUDY AND LITERATURE STUDY COMPARATIVE STANDARD SHEET.
- FINAL THE DESIGN (PLAN ,ELEVATION, SECTION,)
- ELECTIVE.
- 3D VIEW .

## **SWOT ANALYSIS:-**

### **❖ STRENGTH:-**

- ❖ Safe & comfortable atmosphere like home.
- ❖ Great location with highways near it.
- ❖ Sport complex, shopping mall near it.
- ❖ High Profit.

### **❖ WEAKNESS:-**

- ❖ Expensive.
- ❖ High Taxes.
- ❖ Single Brand Strategy.
- ❖ High price of products and services.
- ❖ High Setup Cost

### **❖ OPPORTUNITIES:-**

- ❖ Uniqueness.
- ❖ Dynamic Prices.
- ❖ Local and International Tourists.

### **❖ THREATS:-**

- ❖ Airbnb/Apartment rental industry.
- ❖ Change in trends/consumer behaviour.
- ❖ Pandemics.
- ❖ Strong competition.
- ❖ High Taxes.

# **CHAPTER-02**

## **SITE ANALYSIS**

## **INTRODUCTION (LUCKNOW THE CITY OF NAWABS)**

- Lucknow is the capital and the largest city of the **Indian state of Uttar Pradesh** and it is also the second largest urban agglomeration in U.P.
- Lucknow, the capital of **Uttar Pradesh was founded by Nawab Asaf-ud-Daula**. In the olden times, it served as the capital of the nawabs of Awadh and it is one of the reasons why it is also called as the **City of the Nawabs**.
- In ancient times, Lucknow was known as **Lakshmanpur or Lakhnupur**. Hazratganj known as **“The Heart of Lucknow”**.
- Lucknow is called **Pink City** because every building in **this city is painted by royal majestic terracotta pink**.
- Lucknow stands at an elevation of approximately **123 metres(404ft)** above sea level. The City had an area of **402 sq.km.(155 square miles)** until December 2019, when 88 villages were added to the municipal limits and the area increased to **631sq.km.(244 square miles)**. Bounded on the **east Barabanki**, on the **west by Unnao**, on the **south by Raebareli** and in the **north by Sitapur and Hardoi**.

**LATITUDE:-**-26.883301 ,

**LONGITUDE:-**-80.9826.

- Architecture of **lucknow is mostly Islamic in nature** . It is representative of **18th and 19th century Indian Architecture** . The architecture is broadly divided into **religious architecture** such as that of imanbaras and secular architecture such as that of Baradaris and Kothis.



## FAMOUSLANDMARK

- Attraction makes for a wonderful stroll or picnic. The musical fountains at night, an amphitheatre, dedicated biking area and jogging tracks and boating opportunities definitely make this park a crowd-pleaser.

**LOCATION:-**Jiamau, Lucknow,Uttar Pradesh



**GOMTI RIVERFRONT**

- Rumi Darwaza is a stunning sixty feet tall gateway in the old city of Lucknow. Known for its Awadhi architecture

**LOCATION:-**17/11 Hussainabad Road, Lajpat Nagar Colony, Lajpat Nagar, Machchhi Bhavan, Lucknow, Uttar Pradesh 226003



**RUMI DARWAZA**

- Your Lucknow sightseeing is incomplete without visiting the popular Jama Masjid. 260 pillars and 15 arched domes, the intricate stonework and carvings make it one of the finest mosques in India.

**LOCATION:-**Hussainabad Peer Bukhara, Hussainabad, near Unity College, Lucknow, U.P.



**JAMA MASJID**

- The four-storey Lucknow state museum has some of the finest displays from the stone age, exhibits and galleries showcasing Jain art, sculptures, archaeology, Nawabs and ancient coins.

**LOCATION:-**Narhi, Hazratganj, Lucknow, Uttar Pradesh 226001



**LUCKNOW MUSEUM**

- The heritage trail of the Nawabi city never ends! Welcome to Chattar Manzil, another remarkable monument in Lucknow otherwise known as “Umbrella Palace.”

**LOCATION:-**Mahatma Gandhi Marg, Qaisar Bagh, Lucknow, Uttar Pradesh 226001



**CHATTAR MANZIL**

- **Bara Imambara** is a striking monument that distinguishes itself from all the famous places in Lucknow. The historical landmark is a big complex consisting of the Asfi Mosque, the Bhul-bhulaiya and a Bowli.

**LOCATION:-** Machchhi Bhavan, lucknow. Uttar Pradesh 226003.



**BARA IMAMBARA**

- **Also popular as the Nawab Wajid Ali Shah Zoological Garden**, it is a place to catch hold of some natural splendour within the city. Out of all the amazing tourist places in Lucknow, the zoo will help you discover beautiful wild nature. The zoo was inaugurated on 29 November 1921.

**LOCATION:-** Hazratganj Road, Opp to Civil Hospital, Lucknow, Uttar Pradesh, 226001.



**LUCKNOW ZOO**

- **Ambedkar Memorial Park** is a public area and memorial dedicated to Dr. B. R. Ambedkar. One of the finest tourist places in Lucknow, the park is spread across a massive 107 acres while the monuments inside are made with red sandstone from Rajasthan.

**LOCATION:-** Vipul Khand 2, Vipul Khand 3, Vipin Khand, Gomti Nagar, Lucknow, U.P.



**AMBEDKAR  
MEMORIAL PARK**

- In September 2017, Ekana International Cricket Stadium was opened to the public as it hosted 2017–18 Duleep Trophy. On 6 November 2018 Ekana International Cricket Stadium hosted its first T20 international match between Indian national cricket team and West Indies cricket team.

**LOCATION:-** Amar Shaheed Path, Gomti Nagar, Lucknow U.P.



**EKANA**

- A Residency is a group of several buildings in a residential complex from the Nawab era. Built during the rule of Nawab Saadat Ali Khan II, the residency was part of the 1857 siege of Lucknow.

**LOCATION:-**Mahatma Gandhi Marg, Deep Manak Nagar, Qaisar Bagh, Lucknow, Uttar Pradesh



**THE RESIDENCY**

- Welcome to an urban park in the city meant to rejuvenate the city people. As a tourist, the park would act as a pleasant gift to you. Situated at the city's heart, the park is conceptualized as an eco-friendly zone.

**LOCATION:-**Gomti Nagar, Lucknow, Uttar Pradesh 226010



**JANESHWAR MISHRA PARK**

- The very awesome Anandi Water Park is a recreational zone with thrilling rides, water slides, a wave pool and a lazy river. With a massive fun area and an even bigger resort and club area, it is one of the biggest water parks in India.

**LOCATION:-**Canal Road, Faizabad Rd, beside Indira Canal, Lucknow, Uttar Pradesh 226028



**ANANDI WATER PARK**

- The Stadium has a capacity to accommodate more than 20,000 spectators. The stadium is approved by BCCI to hold first-class level matches and is regularly used for Ranji Trophy matches every year.

**LOCATION:-**Vipin Khand,Gomti Nagar Lucknow U.P.



**BABU BANARASI DAS**

- It is a picturesque strip of road adjacent to the River Gomti in Gomti Nagar, Lucknow.

**LOCATION:-**Marine Drive,Gomti Nagar Lucknow, Uttar Pradesh.



**MARINE DRIVE**

- Situated at the Surajkund Park neighborhood of Lucknow, on the banks of the River Gomti, Indira Gandhi Planetarium is also popularly known as Tara Mandal Show.

**LOCATION:-**Kathauta Chauraha Road, Vibhuti Khand ,Gomti Nagar, Lucknow.



**INDIRA GANDHI PLANETARIUM**

- Built by Nawab Saadat Ali Khan, the Moti Mahal is popularly known as the Pearl Palace. This historical monument located on the banks of river Gomti is constructed next to Mubarak Manzil and Shah Manzil.


**LOCATION:-**Rana Pratap Marg,Hazratganj, Lucknow U.P.



**MOTI**

- Located close to Chhota Imambara and the Hussainabad Clock Tower, Hussainabad Picture Gallery is a popular tourist attraction in Lucknow.

**LOCATION:-**Husainabad Lucknow Uttar Pradesh.



**HUSSAINABAD PICTURE GALLERY**

- The Sikander Bagh is another reminder of the brutality of the “Siege of Lucknow” – which was once the summer residence of the Nawab Wajid Ali Shah.

**LOCATION:-**Ashok Marg, Gokhale Vihar, Civil Lines, Lucknow, Uttar Pradesh 226001



**SIKANDER BAGH**

- Dilkusha Kothi was built in 1800 by Major Gore in Baroque style. It faced major impact during the first war of independence and hence lies in a less than perfect state with just a few towers and walls standing.
- **LOCATION:-**Bibiapur Marg Lucknow



**DILKUSHA KOTHI**

Situated in Aashiyana, the Chandrika Devi Temple is dedicated to the Hindu Goddess Chandi. Adorning three heads, Chandrika Devi is said to be a combined manifestation of Goddesses Kali, Lakshmi and Sarasvati.



**LOCATION:-**Jail Rd,SectorJ,Ashiyana,  
Lucknow, Uttar Pradesh.

#### **CHANDRIKA DEVI TEMPLE**

- The Mankameshwar Mandir is situated on the banks of river Yamuna at Sarasvati Ghat in Lucknow. A revered Hindu temple dedicated to Lord Shiva, this temple is the first to have had a woman priest.


**LOCATION:-**Mankameshwar Mandir Marg,  
Hasanganj,Lucknow,Uttar Pradesh.



#### **MANKAMESHWAR MANDIR**

- Situated in the Barabanki district of Uttar Pradesh, 25 kms away from Lucknow, Dewa or Dewa Sharif is a small town which is renowned world wide for the shrine of Haji Waris Ali Shah.

**LOCATION:-**Dewa near Matyari Lucknow.



#### **DEWA SHARIF**

- The University of Lucknow (informally known as Lucknow University, and LU) is a public state university based in Lucknow, Uttar Pradesh. Founded in 1920, the University of Lucknow is one of the oldest government owned institutions of higher education in India.

**LOCATION:-**Babuganj,Hasanganj,Lucknow



#### **LUCKNOW UNIVERSITY**

- Amity University Lucknow Campus (AULC) is a constituent unit of Amity University, Uttar Pradesh & it was established in the year 2004 with the sole objective to impart research & innovation driven education in the region. total area of university is 40acre.

**LOCATION:-**Malhaur Railway Station Road,  
Gomti Nagar,Lucknow,U.P.



**AMITY UNIVERSITY**

- Babu Banarasi Das University (also known as BBD University) is a private university having its Main Campus in Lucknow, Uttar Pradesh, India established by Akhilesh Das in 2010 and named after his father and former Chief Minister of Uttar Pradesh, B.B.D.U.

**LOCATION:-**Faizabad Rd,Atif Vihar, Lucknow



**B.B.D.U. UNIVERSITY**

- One of the most bustling and oldest shopping hubs of Lucknow, Aminabad is a famous market selling a wide range of products from clothes and jewelry to cosmetics, footwear and even books.

**LOCATION:-**Aminabad, Siraj Dokadia Rd.,  
Aminabad,Lucknow,U.P.



**AMINABADMARKET**

- Chowk market in Lucknow is one of those places of the city that are a window into its rich cultural heritage.

**LOCATION:-** Kanchan Market Chowk,Machchhi Bhavan Lucknow.



**CHOWK MARKET**

- Hazratganj, the central shopping district of Lucknow, has a long history behind it and has undergone a great makeover that bridges the past and the present and continues to serve as Lucknow's central shopping arcade.

**LOCATION:-**Hazratganj Lucknow Uttar Pradesh.



**HAZRATGANJ**

- The Lucknow believe Nakhas Market to be the oldest market and one of the best places for budget shopping at Lucknow. Selling wooden handicraft items; Zardozi embroidered clothes, jewelry and household items.

**LOCATION:-**Nakhaas Market Shayam

Bandhu Shahganj Lucknow,U.P.



**NAKHAAS MARKET**

- Lucknow has a total of 5.66 percent of forest cover. The state average is around 7 percent. Shisham, Dhak, Mahuamm, Babul, Neem, Peepal, Ashok, Khajur, Mango and Gular trees are all grown here. Mangoes, especially Dasherri, are grown in the Malihabad

**LOCATION:-**Malihabad Lucknow U.P.



**MANGO TREE**

- The craft of Chikan work, often referred to as Lucknow Chikan, is over 400 years old with a firm presence in the Indian and global fashion arena.

The technique of its creation is called Chikankari and its unique sensibility flaunts grace and elegance as subtly as the wearer pleases.

**LOCATION:-** Purana Lucknow Chowk



**CHIKANKARI**

## **INTRODUCTION (ABOUT THE TOPIC)**

- A 5 star hotel is a hotel that provides a luxurious experience and high-end accommodations. Five-star hotels are known to be some of the most glamorous **hospitality locations** in the world due to the level of service they provide.
- Five star hotels offer **luxurious decor and carefully selected furnishings with high attention to detail.**
- The **guestroom and suits are tastefully decorated** with high quality furnishings and consistent design, ample space,**large queen or king sized beds, premium bedding and luxurious bath products.**

## **Amenities in addition to the facilities provided by a 5 Star Hotel**

- Speciality Restaurant.
- Coffee Shop.
- Lounge.
- Health club.
- Public Areas.
- Guest room including premium furniture and linen wardrobes,slippers,safe,wet bar.

## **HOTEL(5STAR)**

- It must have a minimum **plot size of 5000 sq.mt.**
- F.A.R. is allowed upto 3 (20-25 of this FAR can be used for commercial purpose).
- Ground Coverage upto**40**
- Parking -**1ECS per 100sq.mt. of covered area.**

## **ROOM SIZE IN FIVE STAR HOTEL**

### **1. DOUBLE ROOM**

- A room assigned to two people. May have one or more beds. The room size or area of Double Rooms are generally between  $40 \text{ m}^2$  to  $45 \text{ m}^2$ .



### **2. SINGLE ROOM**

- A room assigned to one person. May have one or more beds. The room size or area of Single Rooms are generally between  $37 \text{ m}^2$  to  $45 \text{ m}^2$ .



### **3. APARTMENT**

- This room type can be found in service apartments and hotels which target for long stay guests. Open kitchens, cooking equipment, dryer, washer etc. are usually available in the room. Housekeeping services are only provided once in a week or two times in a week. The room size or area of Serviced Apartments are generally between  $96 \text{ m}^2$  to  $250 \text{ m}^2$ .



#### **4. DISABLED ROOM**

- This room type is mainly designed for disabled guests and it is required by law that hotels must provide a certain number of accessible rooms to avoid discrimination. The room size or area of **Accessible Room Types** are generally between **30 m<sup>2</sup> to 42 m<sup>2</sup>**.




#### **5. TRIPLE ROOM**

- A room that can accommodate three persons and has been fitted with three twin beds, one double bed and one twin bed or two double beds. The room size or area of **Triple Rooms** are generally between **45 m<sup>2</sup> to 65 m<sup>2</sup>**.



#### **6. QUEEN ROOM**

- A room with a queen-sized bed. May be occupied by one or more people. The room size or area of **Queen Rooms** are generally between **32 m<sup>2</sup> to 50 m<sup>2</sup>**.



#### **7. HOLLYWOOD TWIN ROOM**

- A room that can accommodate two persons with two twin beds joined together by a common headboard. The room size or area of **Hollywood Twin Rooms** are generally between **32 m<sup>2</sup> to 40 m<sup>2</sup>**.



## **8. MINI/JUNIOR SUITS**

- A single room with a bed and sitting area. Sometimes the sleeping area is in a bedroom separate from the parlor or living room. The room size or area of **Junior Suites** are generally between **60 m<sup>2</sup> to 80 m<sup>2</sup>**.




## **9. QUAD ROOM**

- A room assigned to four people. May have two or more beds. The room size or area of **Quad Rooms** are generally between **70 m<sup>2</sup> to 85 m<sup>2</sup>**.



## **10. KING ROOM**

- A room with a king-sized bed. May be occupied by one or more people. The room size or area of **King Rooms** are generally between **32 m<sup>2</sup> to 50 m<sup>2</sup>**.



## **11. STUDIO ROOM**

- A room with a studio bed - a couch which can be converted into a bed. May also have an additional bed. The room size or area of **Studio room** types are generally between **25 m<sup>2</sup> to 40 m<sup>2</sup>**.



## **12.PRESIDENTIAL SUIT**


- President suite is available in one single hotel property. President suite always has one or more bedrooms and a living space with a strong emphasis on grand in-room decoration, high-quality amenities and supplies, and tailor-made services. the room size or area of **presidential suites** are generally between **80 m<sup>2</sup> to 350 m<sup>2</sup>**.




## **PROJECT SPECIFICATION**

PROJECT BUILDING TYPE	> 5 STAR HOTEL
NATURE OF THE PROJECT	> HOSPITALITY
NAME OF THE CLIENT	> LUXUS HOSPITALITY PVT.LTD.
ARCHITECT	> AR. KAPIL BHALLA & JAYSHREE DARDA BHALLA
LOCATION	> PLOT NO: TC-25V VIBHUTI KHAND GOMTI NAGAR OPP. COMMERCIAL TAX OFFICE LUCKNOW UTTAR PRADESH 226010.
SITE AREA	> 7500SQ.MT.
FRONT(S) SETBACK(N)SETBACK	> 12MT. , 9MT.
(E) SETACK(W)SETBACK	> 9MT. , 9MT.
RAMP WIDTH	> WIDTH 7.5MT(TWO WAY)
ENTRY	> 2
EXIT	> 1
CONSTRUCTION YEAR	> 2012

## IDENTIFICATION OF SITE




INDIA MAP



UP DISTRICT MAP

UPMAP



SITE LAYOUT PLAN



SITE LOCATION



LUCKNOW MAP

## FAMOUS LANDMARK



LULU MALL- 13KM



WAVE MALL- 2KM



PHOENIX PALASSIO- 9.8KM



LUCKNOW UNIVERSITY- 9.1KM



B.B.D.U. - 7.6KM



AMITY UNIVERSITY- 6.1KM



DELHI PUBLIC SCHOOL- 4.2KM



**AMINABAD MARKET- 10.9KM**



**JANPATH MARKET- 9.2KM**



**SAHARA HOSPITAL- 4.2KM**



**BHOOTHNATH MARKET- 3.9KM**



**R.M.L. HOSPITAL- 1.4KM**



**BADA IMAMBADA- 12.3KM**



**ZOO- 8.4KM**



**JANESHWAR MISHRA PARK- 4.8KM**

## APPROCH TO THE SITE



BY BUS



AWADH BUS STATION- 2.6KM.



KESARBAGH BUS STATION- 12.4KM.



ALAMBAG BUS STATION- 16KM.



CITY BUS STATION-



BYRAIL



CHARBAGH RAILWAY STATION-11.5KM.



BYMETRO



INDRIYANAGAR METRO STATION-3.1KM.



BYAEROPLANE



CHAUDHARY CHARAN SINGH  
AIRPORT- 3.1KM


## SITE SURROUNDING



**DR.R. M. L.I.OF  
M.SCIENCE CENTRAL RESERVE POLICE FORCE**




**ELDECO CORPORATE TOWER**



**UTTAR PRADESH  
RAJKIYANIRMAN NIGAM U.P.**



**BOBBANK & ICICI BANK**



**BOB BANK**



**POLICE STATION**



**BHAVYA CORPORATE  
TOWERS**




**PRAGYA DIRECT TAXES  
REGIONAL TRAINING  
INSTITUTE**



**FOOD CORPORATION  
OF INDIA**



**KARYALAYA POLICE  
ADHIKSHAK**



**COM.TAXDEP.  
HEAD OFFICE**

## **SITE CONDITION**



### **THE CLIENT DETAILS**

**CLIENT :-** Luxus Hospitality Pvt. Ltd.

**ESTABLISHED YEAR :-** 09 July 2014.

**AGE OF COMPANY :-** App. 8 Year 5 Month.

**FOUNDER :-** Jean V. Mestriner.

**DIRECTOR :-** Amit Singh, Arpit Kumar Singh.

**KEY MANAGEMENT PERSONNEL :-** Manoj Kumar Adukia.

**PARTNER :-** Iconic Taj Brand.

**REGISTERED OFFICE :-** T-C-25-V VIBHUTI KHAND, GOMTINAGAR, LUCKNOW, UTTAR PRADESH.

**TYPE :-** Unlisted Private Company.

**CATEGORY :-** Company Limited By Shares.

**SUBCATEGORY :-** Non-govt Company.

### **ARCHITECT DETAILS**

**ARCHITECT:-** KAPIL BHALLA AND JAYASHREE DARDA BHALLA.

**COMPANY :-** SE-ARCH STUDIO FOR ENVIRONMENT & ARCHITECTURE  
MUMBAI,PUNE.

**COMPANY ADDRESS :-** 601 Lodha Supremus, Senapati Bapat Marg, Lower Parel , Mumbai , Maharashtra 400013.

**OPENING YEAR :-** 1990.

**AWARD :-** 1- National Winner In Design Coffee Shop & Bar/Pub Categories.(Hotel & Food Service Design Award-2014).

### **2- For Excellence In Hospitality Design.**

(Indian Institute of Interior Designer Awards 1990.)

## **KAPIL BHALLA**

**(Founder and Architect) Bachelor of Architecture(1985)**

Sir J.J. College of Architecture, Mumbai.

Master of Architecture(1987)

University of Illinois at Urbana Champaign,USA.

GraduateScool of Design(2008) Harvard University..



## **JAYASHREE DARDA BHALLA**

**(Founder and Architect)Bachelor of Architecture(1985)**

Sir J.J. College of Architecture, Mumbai.

**Master of Architecture(1989)**

University of Illinois at Urbana Champaign,USA.

**Executive Education**


GraduateScool of Design(2006) Harvard University.Boston,

Massachusetts,USA.



## **FAMOUS PROJECT**

### **RESIDENTIAL :**



**UJJWALA:-**Location:Kolkata,WestBengal  
Completedin2007



**UTALIKA:-**Location:Kolkata,West  
BengalUnderConstruction

**Swissotel**



**SWISSOTEL** :-Location:Rajarhat,Kolkata,West Bengal|Completedin2010

**Makaibari**




**MAKAIBARI** :-Location:Kursoeng,Darjeeling|DesignDevelopment

**Maya**



**MAYA**:-Location:Kolkata,WestBengal | Completedin2011



**ANAYASPA**:-Location:Raichak|Completedin2012

## HOMES

**M House**



**MHOUSE**:-Location:Alibaugh,Maharashtra | Completedin2014



**9A**:-Location:Mumbai,Maharashtra|Completedin2012

## WORKPLACE




**MSC**:-Location: Andheri, Mumbai, Maharashtra | Completed in 2009



**HVN ESO**:-Location:Kolkata,WestBengal | Completedin2015


## CLIMATIC DATA

- The climate of Lucknow is **subtropical**, with a rainy season that runs roughly from **mid-June to early October**, due to the monsoon, and a **dry season** from **mid-October to early June**.
- The city is the capital of the state of Uttar Pradesh and is located in northern India, on the banks of the **River Gomti**, a tributary of the Ganges, and at almost 27 degrees north latitude.
- The best time to **visit Lucknow is from mid November to mid February** being the coolest within the dry season.




## TEMPERATURE GRAPH

- At an average temperature of 32.8 °C/91.1 °F, May is the hottest month of the year.
- In January, the average temperature is 14.9 °C/58.9 °F. It is the lowest average temperature of the whole year.




## PRECIPITATION GRAPH

- The month with the highest number of rainy days is July (18 Days).
- The month with the least rainy days is November.




## RELATIVE HUMIDITY GRAPH

- The month with the highest relative humidity is August (78%).
- Month with the lowest relative humidity are April and May (35%).




## SUNSHINE GRAPH

- Lucknow, the month with the most daily hours of sunshine is May with an average of 11.9 hours of sunshine. In total there are 369.01 hours of sunshine throughout May.
- The month with the fewest daily hours of sunshine in Lucknow is January with an average of 8.99 hours of sunshine a day. In total there are 278.75 hours of sunshine in January.




## WIND SPEED GRAPH

- A monthly average wind speed of over 16km/h or 10mph suggests a location is fairly windy.
- The windiest month (with the highest wind speed) is June (10km/h).
- The windiest month (with the lowest wind speed) is November & December (3km/h).




## DAY NIGHT TEMPERATURE GRAPH

- Orange colour graph shown day temperature graph. Blue colour shown night temperature graph.
- May is the hottest month ( $32.8^{\circ}\text{C}$ ) in Day and ( $25^{\circ}\text{C}$ ) in night.





## WIND ROSE MOVEMENT

- The wind rose for Lucknow shows how many hours per year the wind blows from the indicated direction. Example SW: Wind is blowing from South-West (SW) to North-East (NE).



## SUNPATH DIAGRAMS

- Sun Path Diagram can tell you a lot about how the sun will impact your site and building throughout the year.
- Stereographic sun path diagrams can be used to read the solar azimuth and altitude for a given location.



## **REQUIREMENT OF PROJECT**

### **GROUND FLOOR:-**

- BANQUET LOBBY.
- LOBBY & V.I.P. LOUNGE.
- BANQUET(2).
- TOILET.
- CIRCULATION.
- PRE FUNCTION.
- OPEN OUTDOOR LAWN.
- KITCHEN(STORE).
- STORE/DISH WASH.

### **FOOD & BEVERAGES:-**

- CONFERENCE(3).
- KITCHEN.
- ALL DAY DINING.
- KITCHEN.
- SPECIALITY CUM BAR.
- TIOLET.
- CIRCULATION.
- AQUARIUM.
- PRE FUNCTION.
- BELOW BISTRO.
- BELOW RECEPATION/WAITING.

### **MEZZANINE FLOOR:-**

- STAIR.
- LIFT.
- MALE BUNKER ROOM.
- MALE/FEMALE LOCKER ROOM.
- RELAXATION AREA.
- UNIFORM CHANGING ROOM.
- STAFF PANTRY.
- STAFF CAFETERIA.
- LIFT LOBBY/STAIR.
- KITCHEN/STORE.
- CORRIDOR.

### **DESIGN LIMITATIONS**

- ENTRANCE LOBBY
- SINGLE ROOM.
- JUNIOR SUIT.
- PRESIDENTIAL SUIT.
- CONFERENCE HALL
- ALL DAY DINING

## **HOTEL AREA DEFINED**

### **PUBLIC AREA:-**

- LOBBY + RECEPTION
- RESTAURANTS
- LOUNGE + BAR
- CLOAK ROOM
- PARKING
- RECREATIONAL AREA (OUTDOOR).
- BANQUET

### **PRIVATE AREA (GUEST)**

- SINGLE BEDROOM
- DOUBLE BEDROOM
- DELUXE BEDROOM
- SUIT BEDROOM
- STEAM ROOM + SPA
- LOUNGE + BAR
- READING
- RECREATIONAL AREAS (SWIMMING POOL)



## **PRIVATE AREA(STAFF)**


- ADMINISTRATION OFFICE
- ACCOUNTS OFFICE
- TECHNICAL/MECHANICAL ROOM
- LAUNDARY + STORAGE
- KITCHEN + STORAGE
- CONTROL ROOM
- WASTE DISPOSAL
- LOCKERS + WASHROOM
- PANTRY

### **SEMI PRIVATE**

- BANQUET
- DINING HALL
- MULTIPURPOSE HALL

## ACTIVITY FLOW CHART OF SPACES IN HOTEL







**KEY PLAN**



## **GROUND FLOOR PLAN**




## **GROUND FLOOR BUBBLE** **DIAGRAMME**




## **FOOD & BEVERAGES PLAN**





**MEZZANINE FLOOR PLAN**



**MEZZANINE FLOOR PLAN BUBBLE DIAGRAM**

# **CHAPTER-03**

**LITERATURE STUDY -01**

**AVASA HOTEL HYDERABAD**

## **AVASA HOTEL HYDERABAD**

### **INTRODUCTION**

- The 15-storey Hotel Avasa is a modern 5-star property offering luxurious accommodation in Hyderabad. It has 4 dining options, a health club and a tour desk.
- Avasa Hotel is designed by nandu associates and poole Associates and take on unique architecture, interior, and contemporary design. This well appointed, 5 star accommodation has 11 floors and houses 217 rooms and suites fit for guests with modern needs and a desire for luxury. The hotel has 17000sq.ft. of banquet and convention space . The three dining option include Pi for all day dining and sky for the bar and lounge with vast arrays of drinks available. Avasa Hotel is the ideal accommodation providing outstanding services and the best facilities in Hyderabad.




**EXTERIOR VIEW AVASA HOTEL**

## **SILENT FEATURES**

- The hotel AVASA was established in the year 2012. It was owned by **STAMLO HOTELS GROUP**
- Hotel AVASA was established to **meet the demand of software people and tourists visiting hyderabad.**

## **CONCEPT**


- Highly site-specific scheme
- The site is wide towards the front road and narrows downwards towards the back.
- The building follows the site, forming the letter 'A', in plan.
- Due to limited open space on site, continuous green space has been conceived in the form of stepped terraces - third level to the top.




**A CONCEPT AVASA  
HOTEL**

## **DESIGN**

- It was well designed in a small site.
- The interrelationship of different areas of the **back of the house** and **front of the house** and their co-relationship with each other
- It was designed such an aesthetically with stepped terrace gardens with respect to the site.
- The irregular shaped site was the biggest design challenge
- 98% of the lighting being led. Avasa is a highly environment friendly.



## LOCATION



AVASA HOTEL HYDERABAD GOOGLE EARTH VIEW

## **PROJECT DETAIL**

- **Architects:** Nandu Associates
- **Location:** Madhapur, Hyderabad, India
- **Team:** B. Nanda Kumar, Ankita Gupta, B.H.Ravi Shankar, B.Naveen Reddy
- **Area:** 8179.0 sqm( app.2 acres)
- **Project Year:** 2012
- **Interior designer:** EdPoole from Singapore.
- **Landscape design :** Design cell studio
- **Floor :** 15
- **Owner :** Avasa Enterprises Private Limited.
- **Director :** Karthik Miryanam And Ganesh Miryanam
- **F.A.R. :** 2.5
- **Build up Area :** 21,120sq.m.
- **Ground Coverage :** 50

## **CLIMATE**

- The climate is Arid. Average temperature range from 15°C - 40°C. Depending upon weather.
- Mar–Jun is very hot, before the Jul–Sep peak monsoon rains. Nov–Feb is dry, with warm days and mild evenings.

## **2 ATRIUMS :-**

- Lobby atrium at Ground Level,Central atrium at third level.

## **2 BRIDGES :-**

- 5th Floor Business club bridge,Double level sky bar at 10th and 11th level.

## **ABOUT**

- The nine room floors sit on a podium containing the arrival porte-cochere, the **reception lobby, a specialty restaurant and all-day dining.**
- The first level contains the banqueting facilities including the Grand Ballroom which is connected directly to the ground level porte-cochere by a **grand staircase**.
- The **second level** is the service floor over the **banquet corridors**.
- The **third level** has the first room floor with **spa and gym**.
- The **central atrium space** opens out to the pool deck and **terrace function space with alfresco bar**.
- The **stepped terraces** at each higher floor have been given a different character - experience the **naturally lit corridors and the lush cascading gardens**.
- Brings together contemporary style with time tested service.
- Rooms are arranged along the two arms of the “A” and the connecting slab between the twms acts as terrace space which step back as one goes to the higher levels.
- Vertical transport through this stepped section is achieved through 3 separate banks of lifts.



## **SITE PLAN AND ANALYSIS**

**SITE:**The site is wide towards the road and narrows downwards towards the back.

**BUILDING:**The building is a “A”shaped plan which was planned according to the site.

## **PARKING**

- For 250 cars \$ 500 four wheeler
- Surface parking is provided officially some carparked on the surface to.
- 3 Basement were used for public and staff parking
- Ramp Ratio - 1:10



## **MATERIALS AND GREEN IDEAS**

- The stepped elevation faces north, bringing in natural north light into the atrium and enhances energy efficiency. Granite used for flooring and cladding throughout the property have been sourced from local sites reducing the carbon footprint. The flooring for the main lobby and banquet halls is quartz .
- Masonry and non-load bearing partition walls. Main advantages of using these bricks being reduction of dead loads, saving structural costs and faster construction. Aluco-bond/Metal cladding was deliberately kept to the bare minimum

## SITE PLAN

### INTERIOR IMAGES



## FAMOUS LANDMARK



**NEHRU ZOOLOGICAL PARK-28KM.**




**CYBER TOWERS-3KM.**



**CHARMINAR - 19.7KM.**



**PACE HOSPITAL - 67M.**



**E GALLERIA MALL - 290M.**



**SHILPARAMAM- 1.3KM.**

## ACCESS TO THE SITE



**BYBUS**



**MAHAMATA GANDHI  
BUS STATION-17KM.**



**BYRAIL**



**SECUNDERABAD RAILWAY  
STATION - 16 KM.**




**BYAEROPLANE**




**RAJIV GANDHI INTERNATIONAL  
AIRPORT-24KM.**

## FLOOR PLAN



## GROUND FLOOR PLAN

- |                               |                                     |
|-------------------------------|-------------------------------------|
| 1- Entrance porch             | 2- Lobby(172.7sq.m.)                |
| 3- Reception(40sq.m.)         | 4- Back office(131.8sq.m.)          |
| 5- Restaurant(240sq.m.)       | 6- Kitchen 1 & 2 (206sq.m.,35sq.m.) |
| 7- Add Restaurant(468.8sq.m.) | 8- Service area(96.08sq.m.)         |
| 9- Grand Staircase            | 10- Administrative area(125.8sq.m.) |




## **THIRD FLOOR PLAN**

- |                                |                             |
|--------------------------------|-----------------------------|
| 1- Pool (500.45 sq.m)          | 5- Rooms (606.56 sq.m)      |
| 2- Terrace plaza (726.69 sq.m) | 6 Lounge (74.66 sq.m)       |
| 3- Gym (166.8 sq.m)            | 7 Boardroom (95.75 sq.m)    |
| 4- Spa (161.1 sq.m)            | 8 Service area (96.08 sq.m) |
|                                | 9- Terrace bar (188.3 sq.m) |




## **FORTH FLOOR PLAN**

1. Rooms
2. Service area (96.8 sq.m)




## **FIFTH FLOOR PLAN**

1. Rooms
2. Service area (96.8 sq.m)
3. Private meeting area (16 sq.m)
4. Business club lounge (180 sq.m)



## **SIXTH FLOOR PLAN**

1. Rooms
2. Service area (96.8 sq.m)
3. Private meeting area (16 sq.m)
4. Stepped level seating (74 sq.m)




## **SEVENTH FLOOR PLAN**

1. Rooms
2. Service area (96.8 sq.m)
3. Private meeting area (16 sq.m)



## **EIGHTH & NINTH FLOOR PLAN**

1. Rooms
2. Service area (96.8 sq.m)
3. Private meeting area (16 sq.m)



## **TENTH FLOOR PLAN**

1. Rooms
2. Service area (96.8 sq.m)
3. Bar pantry (64.3 sq.m)
4. Sky bar (208.6 sq.m)



## **ELEVENTH FLOOR PLAN**

1. Rooms
2. Service area (96.8 sq.m)
3. Kitchen (64.3 sq/m)
4. Rooftop restaurant (208.6 sq.m)




## **SECTION**


The building sections were the most important detail in the design process. The section, through the terraces explains the buildings spatial qualities at its best. The spatial drama is created by the receding terraces that seem to invite the elements right to its core.




SECTION 1-SECTION THROUGH TERRACE AND CENTRAL PLAZA




SECTION 2-SECTION THROUGH CENTRAL PLAZA FACING TERRACE



### SECTION 3-SECTION THROUGH GRAND STAIR-CASE



## **NORTH SIDE ELEVATION**



## **WEST SIDE ELEVATION**


## **LIGHTING**

The stepped elevation faces north, bringing in natural north light into the atrium and limiting energy use. With 98% of the lighting being LED, Avasa is a highly environment friendly property.



For the grand ballroom, a post tensioned slab of 300mm thickness was conceived to create shallow beams and provide more clear height. A vierendeel frame structural system was used for the stepped terrace to make them self supporting. The Sky bar also uses a three floor vierendeel frame system. This was used as there were large spans from 14m to 25m.

**MATERIALS USED:** Stones used for flooring. Aluco-



## **STRUCTURAL SYSTEM**

## INTERIOR DETAILS

### GYM

- Area: 166.8 sqm
- Capacity: 20 people



### SWIMMING POOL

- Area: 500.45 sqm



### SPA

- Area: 161.1 sqm
- Capacity: 20 people



## CONFERENCE HALL

### **1.MEET ORION:-**

**Boardroom**

**AREA:-** 74 sq.m.

**SEATS:-** 25 seater Situated away from disturbances.



### **2.MEET OMNI:-**

**Boardroom/ Classroom**

**AREA:-** 70 sq.m.

**SEATS:-** 25 seater.



### **3. NOVA :-**

**AREA:-** 145.8 sq.m.

**100 seater** (wall equipped and wellmanned).



### **4.VEGA:-** **Ball room**

**AREA:-** 186.27 sq.m.

**140 seater.**



### **5.CONSTELLAN :-**

**Ball room**

**Area:-** 532.3 sq.m.

**Seater -** Upto 550 people in theatre arrangement.

## AIR CONDITIONING

- The whole structure is centrally air conditioned
- Fan coil units are provided in each room to control the quantity and quality of air.
- C.A.C. Plant room is on the lower basement D.Height-6 meters.
- Chilled water used as refrigerant



## BANQUET HALL

- 3 FIRE EXITS WITH AN AVERAGE DISTANCE OF 50 M BETWEEN THEM.
- SERVICE CIRCULATION GROUND FLOOR- 258.12.
- PUBLIC TOILET

MALE -4WC, 3URINAL, 2WB



FEMALE-4WC, 2WB.

- THIRD FLOOR PUBLIC TOILET.

MALE- 2WC, URINAL , 1 WB.



FEMALE - 3 WC , 1 WB.

## RESTAURANT AND BAR

### **1. ALL DAY DINING:-**

- 24 Hour Restaurant
- Area: 468.8 sqm
- Capacity: 100 people



## **2. OHM-ASIAN CUISINE**

- Oriental Food
- 9:00 to 11:00 hrs
- Area: 240 sqm
- Capacity: 70




## **3. BRIDGE BUSINESS CLUB**

- Lounge + Bar
- Formal
- Area – 180 sqm
- Capacity – 45



## **4. SKY LOUNGE**


- Lounge + Bar
- Informal
- Area – 208.6+123.5 sq.m.
- Capacity – 70+50



## **PROPERTY AMENITIES**

- PI- ALL DAY DINING RESTAURANT
- OHM-ORIENTAL SPECIALITY RESTAURANT
- BRIDGE- THE CLUB LOUNGE
- SKY-THE LOUNGE B
- SPA
- GYMNASIUM
- SWIMMING POOL
- AMPLE PARKING
- ROUND THE CLOCK FRONT DESK
- SAFE DEPOSITS LOCKERS
- BUSINESS CENTER
- CONVENTION HALL


## CIRCULATION



## **GUEST ROOMS TYPES**

	No of Users	Area (sq.m)	No of Rooms	Total Area (sq.m)
Avasa Silver	2	42	110	4620
Avasa Platinum Club	2	42	100	4200
Avasa Studio Suite	2	52	5	260
Avasa Gallery Suite	2	82	2	164

- Room – 35 sqm
- Toilet – 7 sqm
- No of room- 104
- LCD TV
- iPod docking station
- Wired & wireless broadband internet access
- Electronic safe
- Personal bar
- Iron Board
- Complimentary Buffet Breakfast



**AVASA SILVER ROOM VIEW**


**AVASA SILVER LAYOUT**

## **MATERIALS:-**


After a hectic day, tune in to the latest movies or shows on the 32-inch flat screen TV. Have a good night's sleep in your well-appointed room that has a pillow menu. Designed lavishly, the ensuite bathroom comes with marble flooring.

## **ROOMS: AVASA PLATINUM CLUB**

- Room-35 sqm
- Toilet-7 sqm
- No of room- 101
- LCD TV iPod docking station Wired & wireless broadband internet access
- Electronic safe.
- Personal bar
- Iron Board Complimentary Buffet Breakfast
- One Way Airport Conveyence Media Hub, HappyHour cocktails at Bridge Business Club



**AVASA PLATINUM CLUB  
VIEW**





**AVASA PLATINUM CLUB LAYOUT**

## **MATERIALS:-**


- These rooms are big, having big windows
- A study table along with a chair provided in these rooms help business travellers to complete their work comfortably. LED lights used in these rooms make them look bright and vibrant. Each room features minimalistic furniture. The rooms are spacious, well-furnished, have elegant wooden interiors along with attached bathrooms and all modern facilities.
- Plywood and fabric bed back wall design. Pure white Paint .
- Toughened glass window with Grey Cotton Curtain .

## **ROOMS: AVASA STUDIO SUITE**

- Room-40 sqm,
- Toilet-12 sqm
- No of room- 4
- LCD TV
- iPod docking station Wired &wireless broadband internet Electronic safe,
- Personal bar
- Iron Board Complimentary Buffet Breakfast An hours' use of the
- Meeting room Two way Airport conveyance



**AVASA STUDIO  
SUITE ROOM VIEW**




**AVASA STUDIO SUITE LAYOUT**

## **MATERIALS:-**

- Each room features minimalistic furniture and simple appeal.
- The rooms are spacious, well furnished have elegant wooden interiors along with attached bathrooms and all modern facilities

## **ROOMS: AVASA GALLERY SUITE**

- Room-70sqm,
- Toilet-12sqm
- No of room- 8
- LCD TV,
- IPod docking station,
- Wired & wireless broadband
- Internet Electronic safe.
- Personal bar,
- Iron Board
- Complimentary Buffers Breakfast 2 hours use of the Meeting room Two way Airport conveyance  
Complimentary Cocktails



**AVASA GALLERY SUITE LAYOUT**

## **AREA ANALYSIS**

ENTRANCE LOBBY	270.423SQ.M.	25	BOARDROOM 1	74SQ.M.	20
BACK OFFICE	83.18 SQ.M.	12	BOARDROOM 2	70 SQ.M.	20
SERVICE AREA	210 SQ.M.	30	GYM	166.8 SQ.M.	20
RESTAURANT 1	468.8 SQ.M.	100	SPA	161.1 SQ.M.	20
KITCHEN 1	210.2 SQ.M.	,	SWIMMING POOL	500.45 SQ.M.	,
SERVICING AREA	96.08 SQ.M.	,	ROOM 1	35 SQ.M.	2

# **LITERATURE STUDY - 02**

**VIVANTA TAJ**

**WHITEFIELD BANGALORE**

## **VIVANTA TAJ WHITEFIELD BANGALORE**


### **PROJECT DETAIL**

- Architects: WOW Architects | Warner Wong Design
- LOCATION: Whitefield, Bangalore, Karnataka,
- India Collaborator: Spazzio Design Architecture
- Client: The Indian Hotels Company Limited
- Area: 19638 SQ.M
- Project Year: 2009
- Photographs: Aaron Pocock
- CATEGORY :- HOTELS
- Located 45 Km Away from the Airport, 18 Km. Away.
- From the CBD of the city
- Gateway statement between the IT Park and the developing city around it.





## CONCEPT

- Landscaper Over Skyscraper – Mobius Strip
- Designed As A Flowing Land-scrapper That Blends Earth To Sky
- Spaces Flow And Connect To Each Other Encouraging Exchange And Interaction.



## INTRODUCTION

- The word symbolizes life and being alive.
- VIVANTA inspired from “Bon Vivant” speaks of style scophistication and refineent.
- Vivanta by Taj – Whitefield, Bangalore rose above 180 global entries to win 'Building of the Year', and 'Interior Design Award' and 'Architecture Award' in the Hotel and Commercial categories at the 2010 Singapore Institute of Architects Design Awards.
- A naturally ventilated rooftop bar opens out onto landscaped gardens that form part of a **green roof**. Rainwater is harvested for landscape irrigation. Composition of highly reflective dark/light tinted glass alludes to the memory of the original site and achieves OTTV values without compromising room views.
- Standing at the Main entrance to the International Teach Park Bangalore (ITPB).



## **PLANT AND MACHINERY**

- Screw Chillers – 250 Tr X 03 No's – Kirloskar
- Dg Set's – 750 Kva X 02 No's – Cummins
- Transformers – 1000 Kva X 02 No's
- Hot Water Boilers – 2 Lacs K. Calories Per Hour
- 10 Kl Per Hour – Ro Plant For Water Treatment
- Sewage Treatment Plant – 200 Kl Per Day



## **AWARD**

- Leaf Design awards for the best commercial building World Wide 2012.
- Singapore President's Design award for Hotel Design.
- Travel and Leisure Award 2011- Top 2 Hotels in India.
- Building of the year (SIA) Architectural Design Awards 2010.
- Architecture Design Award, Singapore Institute of Architects Awards.
- IAD Best Architect, Hospitality 2009.
- IAD best Interior designer 2009.
- Trip Advisor top 10 trendiest hotels 2012.

## LOCATION



INDIA MAP



BANGALORE MAP



VIVANTA BY TAJ GOOGLE EARTH VIEW

## NEAREST LANDMARK



PARK SQUARE MALL- 90M.



NANDINI RESTAURANT - 480M.



NARAYAN MULTISPECIALITY  
HOSPITAL - 510M.



LOCAL CITY SUPER  
MARKET - 790M.

## ACCESS TO THE SITE



M.G. ROAD METRO  
STATION- 550M.



BANGALORE EAST RAILWAY STATION(2KM)



BYMETRO



BYRAIL




BYAEROPLANE



KEMPEGOWDA INTERNATIONAL  
AIRPORT(35.9KM.)

## **FLOOR PLANS & SECTION**




GROUND FLOOR PLAN

5m 10m 20m



## **GROUND FLOOR PLAN**




1ST FLOOR PLAN

5m 10m 20m



## **1ST FLOOR PLAN**




2ND FLOOR PLAN

5m 10m 20m



## 2ND FLOOR PLAN




3RD FLOOR PLAN

5m 10m 20m




## 3RD FLOOR PLAN



4TH FLOOR PLAN


## 4TH FLOOR PLAN

5m 10m 20m




## NORTH ELEVATION

5m 10m 20m




**SECTION THROUGH BAR LOUNGE**

5m 10m 20m




**SECTION THROUGH LOBBY**

5m 10m 20m



**SECTION THROUGH POOL**



**SOUTH ELEVATION**



**SOUTH ELEVATION**

## **RECREATIONAL SPACES**

### **FITNESS CENTRE**

- Open 24 hours instructor available from 6:30 a.m. to 9:00 p.m.
- Equipped with Life Fitness circuit training and cardio machines.
- Personal training.
- Yoga & Aerobics in an exclusive area adjacent to the gym.
- Wooden flooring.
- Ceiling is simple of gypsum board with chandelier and cove light.
- Walls have cream plastic paints most of wall is glazed.



### **THE EQUIPMENT INCLUDES**

- 3 Treadmills.
- 2 Static cycle
- 1 EFX
- 1 Stepper.
- Free weights
- 7 Individual single station machines.
- 2 Flexible machines for anterior and posterior thigh muscles
- Flat bench.
- Incline and decline bench.



### **POOL - CELSIUS**

- Dimensions  
Length- 25.15 Meters, Width- 10.75 Meters, Depth- 1.2 Meters
- A separate KIDS Pool - Length - 25.15 meters, Width- 3 Meters, Depth- 0.18 to 0.65 Meters.
- Water treatment plant with chlorination
- Timings : 6 a.m. to 9 p.m.




**POOL VIEW**

## SPA - JIVA

- 3 treatmentsuites.The suites have been innovatively
- designed around a soothing garden.

**Prithvi (192sq.ft.),Vayu(192sq.ft.),**

**Akash(192sq.ft.).**



- Relaxation rooms with two heated loungers
- A beauty salon
- Separate steam and sauna room.
- Changing rooms and personal amenities.
- Wooden flooring.
- Louvers and gypsum board ceiling.
- Walls have cream colored plastic paints.



**SPA INTERIOR VIEW**

## LOUNGE - RHYTHM

- You will find RhythM near the Fitness centre.
- This lounge presents a stunning view of the pool.
- Flooring has carpets and rugs under seating stations.
- Ceiling is simple of gypsum board with cov lights.
- Walls have dark maroon plastci paints.
- Contemporary Furnitures.





## **EATING SPACES**

### **TERRACOTTA - INDIAN RESTAURANT**

- Indian Specialty Restaurant
- Open interactive Kitchens
- Hours:

Lunch: 12pm-2:45pm Dinner: 7pm-11.30pm

- Patterned marble flooring
- Light and dark brown colored wooden panels used in the ceiling with ceiling mounted lights .
- The ceiling panels fall on the walls covering the entire exposed part of the wall.
- Entrance wall has textured wall.
- Furnitures are modern contemporary.



**TERRACOTTA RESTAURANT INTERIOR VIEW**


## **TEASE - THE BAR**

- The high-octane bar
- Eclectic style-modern interiors designed with an Indian contemporary feel enhanced in the artwork inside.
- Replete with mirrors and rough textured walls.
- **3 zones:RESTAURANT , BAR, HIGH ENERGY ZONES**
- Hours-3pm to 12am
- Wooden flooring
- Gypsum board ceiling with dramatic cut outs which are lit with cove lights
- Walls are textured giving rustic feel.
- Highlighted columns with same rough textures.



## **CARAMEL - THE DELICATESSEN**


- Indoor and Outdoor seating-view
- Park and enjoy the climate
- Cuisine type: Bakery, Confectionary, Frappes and Smoothies, Homemade ice creams,
- Souvenir & Patisserie.
- Hours: 24 hrs
- Walls are plain white colored
- Very chic ambience
- Super glossy Italian marble flooring
- Gypsum board ceiling with grooves which are lit with cove lights



**TEASE THE BAR**

## **LATTITUDE - ALL DAY DINER**

- Corner from the lobby.
- Inside outside experience for the salubrious climate of the city.
- Open interactive kitchens with display counter,moodlighting,HD TV.
- Hours:- 24 hours.
- Italian Marble flooring
- Maroon and dark brown colored ceiling with ceiling mounted lights.
- Walls have cream colored plastic paints and rest wall are glazed.



**LATTITUDE – ALL DAY DINER**

## EXTERIOR MATERIAL

- Workmanship defects embraced- raw rustic.
- Bush hammer finish enhancing or hide the texture of exposed concrete.
- In places where conc. is inappropriate stone or timber paneling.
- Flux lines embedded in concrete interior and exterior symbolize brand avoid/conceal expansion joints.
- All local materials to avoid carbon expenditure
- Ground plane become green roof,LED light used in exterior elevation.
- Highly reflective glass with dark and light tinted ones save energy.



**CONCEPT PRIMER**




TINTED REFLECTIVE GLASS



PV REFLECTIVE GLASS



SPANDREL REFLECTIVE GLASS



## **CHARM OR DELIGHT**

- Charm Suite-327 sq. ft.
- Bathroom - 70 sq.ft.
- Television-32" LCD TV screen with home theatre system and surround sound to personalize your entertainment.
- Ergonomically designed study table and chair.
- WALLS have cream colored plastic paint, few spaces have niche which have plant pots.
- Gypsum board false ceiling with few track lights, cove light and have plant pots. down lights with ceiling mounted AC.
- Bed has plain MDF board bed back and use of cove lights to accentuate the space, with a chic rug to give a cosy vibe.
- Furnitures are modern themed.
- Italian marble flooring.
- Bathrooms with shower cubicles(rain shower).



**CHARM OR DELIGHT VIEW**

## **ALLURE SUITE**


- Deluxe Allure Suite-447 sq.ft.
- Bathroom- 62 sq.ft.
- Access to Rhythm Lounge .
- All the Services provided for Charm and Delight.
- WALLS have cream colored plastic paint, few spaces have niche which have plant pots .
- Gypsum board false ceiling with few lights, cove light and down lights with ceiling mounted AC.
- Bed has plain MDF board bed back and use of cove lights to accentuate the space, with a chich rug to give a cosy vibe.
- Furnitures are modern themed.
- Italian marble flooring.



**ALLURE VIEW**

## **LOFT SUITE**

- Loft Suite- 770 sq.ft.
- Bathroom- 75 sq.ft.
- Double level room .
- Access from upper level.
- All services as seen in Allure Suite.
- Pool.
- Lower level includes Bedroom and Toilet.
- Upper level includes Living Room, Toilet and study space.
- Material are same as allure suite



**LOFT SUITE VIEW**

## **PRESIDENTIAL NIRVANA SUITE**


- Presidential Nirvana suites - 970 Sq.ft.
- Bathroom-
- Double Level.
- All service provided for Temptation Suite.
- Access from upper level.
- Walls have cream colored plastic paint with blinds at window.
- Gypsum board false ciling with few down lights cove lights with ceiling mounted A.C.
- This suite has small pantry section with all necessary amenities along with dining area and a chic living area.
- Entire floor is covered with area carpet.
- Bed back is made of MDF board and the back wall has two down lights creating a little drama to the entire space.



**PRESIDENTIAL NIRVANA VIEW**

## **TEMPTATION SUITE**

- Premium temptation Suite- 770 sq.ft.
- Bathroom- 75 sq.ft.
- Double level room .
- Access from upper level.
- Wall have light blue colored plastic paint giving a cool hue vibe.
- Gypsum board false ceiling with few down light.Cove lights with ceiling mounted A.C.
- This suite has small pantry nsection with a necessary amenities.
- Italian marble flooring same as other suites.



**TEMPTATION SUITE VIEW**

# **CHAPTER-04**

**CASE STUDY-01**

**GOLDEN TULIP HOTEL, LUCKNOW**

## **GOLDEN TULIP HOTEL LUCKNOW**

### **INTRODUCTION**

- Golden Tulip, Lucknow is an established contemporary business hotel that is located in proximity to commercial and business hubs. This 4-star hotel adheres to international standards in hospitality, making it the most preferred and convenient option for business/leisure travellers. It is located on the Station Road.
- The property offers fitness centre with personal trainers and a swimming pool. The hotel has a multilingual hotel staff, 24-hour concierge service, laundry/dry cleaning/pressing services, WIFI, currency exchange and valet parking facility. For carrying out business deals/meetings, the hotel houses a spacious business centre with work stations and large banquet spaces and excellent A/V equipment.
- The hotel houses 115 contemporary rooms that separate into two wings namely Deluxe and Club. There are four categories of rooms i.e., Superior, Deluxe, Club and Suite.
- Golden Tulip offers excellent dining options. Branche offers Continental and Asian cuisine served in Buffet style and A-La-Carte. Lounge Bar offers premiere spirits and wine. The Oriental Wok offers Pan-Asian, Thai and Chinese Cuisines. Just Baked offers delectable confectionaries and pastries. One can also avail the in-room dining service.



**EXTERIOR VIEWS**



**WING B**



**WING A**



**NIGHT EXTERIOR VIEWS**



**GYM INTERIOR VIWE**

## PROJECT DETAIL

- **LOCATION:** 6 Station Road ,Hussainganj Lucknow.
- **ARCHITECT :-** Ar. Danya Singh
- **CLIENT:** Louvre Hotels SAS + Groupe du Louvre.
- **AREA:** 4527 SQ.MT.(1.12 ACRE)
- **CATEGORY :-** HOTELS
- **FLOOR :-** 9
- **PART :- 2 (WING A AND WING B)**

## ACCESS TO THE SITE



**BY BUS**



**ALAMBAGH BUS STATION - 5KM.**



**BY RAIL**



**LUCKNOW RAILWAY STATION - 2KM.**



**BY AEROPLANE**



**CHAUDHARY CHARAN SINGH  
INTERNATIONAL AIRPORT - 12KM.**

## NEAREST LANDMARK

Nearby commercial landmarks include United bank of commerce (260 metres), Tata Motors (270 metres), Bank of Baroda (300 metres), Home Credit India Finance Private Limited (400 metres), Passport Seva Kendra (650 metres) and Vidhan Sabha (1 km).




**VIDHAN SABHA - 1KM.**



**BANK OF BARODA - 300M.**


## FAMOUS LANDMARK




**LUCKNOW ZOO - 3KM.**



**THE RESIDENCY - 4KM.**



**CHATTAR MANZIL - 4KM.**



**RUMI DARWAZA - 6KM.**




**HAZRATGANJ CHAURAHA - 1.9KM.**



**CHOTA IMAMBARA - 7KM.**

## **LOCATION**



## INDIA MAP

## INDIA




## LUCKNOW MAP




GOLDIN TULIP GOOGLE EARTH VIEW

## **DRAWING DETAILS**

## **FLOOR PLAN WING B**




## **SITE PLAN**



## SECTION 01


## SECTION 02




WING B SITE PLAN




GROUND FLOOR




FIRST FLOOR




## SECOND FLOOR




## THIRD, FOURTH AND FIFTH FLOOR




SIXTH FLOOR







## SECTION BB'



## SECTION CC'





SECTION DD'




POOL VIEW


## FLOOR PLAN WING A



**FRONT ELEVATION**




## BACK ELEVATION




## SIDE ELEVATION


## **SITE SECTIONS**




## SECTION S-1




## SECTION S-1



**SECTION S-3**




**SECTION S-4**



**SECTION S-2**

## **RECEPTION & WAITING INTERIOR VIEW**



## **MATERIAL**

**FLOORING – TILE – ULTRA HIGH GLOSSY – 70X1500 SIZE IN ALL DAY DINING**

**WALL- TOUGHED GLASS & MDF JAALI FOR PARTITION3D PANELS SED IN TV WALL**

**CEILING- PLASTICS DESIGNER SHEETS+ACP SHEETS+POP CEILING+CEILING  
LIGHT+COVELIGHT+HANGING PENDENT**

**SANITARY FITTINGS- TOTO COMPANY**

**FURNITURE- PLY BOARD, WOODEN ACP, STEEL FINISHED ACP, LINEN FABRIC+FOAM**

**FLOOR- HIGH GLOOSY MARBLE IN RECEPTION HEAVY DUTY TILES IN PARKING**

## **BANQUET HALL & CONFERENCE ROOM**



**FLOORING – TILE – AND COVER THE CARPET AND WASHROOM – CERAMIC TILE  
WALL-GLAZING WALLPAPER CURTAIN AND PLYBOARD AND WOODEN TEXTURE  
LAMINATE SHEET .**

**CEILING-GYPSUM BOARD FALSE CEILING , CEILING LIGHT , COVE LIGHT , HEAVY  
CHANDELIER .**

**SANITARY FITTINGS- TOTO COMPANY**

**FURNITURE- PLY BOARD, WOODEN ACP, STEEL FINISHED ACP, LINEN FABRIC+FOAM**

## POOL AND POOL ENTRANCE LOBBY VIEW



## MATERIAL

**FLOORING – TILE – WOODEN PLANKS AND POOL TILES**

**WALL- PAINTS AND WALLPAPER , WALL TILES**

**SANITARY FITTINGS- TOTO COMPANY**

**FURNITURE- PLY BOARD, WOODEN LAMINATES , WHITE LAMINATES**

**WINDOWS- FIX TOUGHED GLASS WITH OPENABLE DOORS**

**ARTIFICAL PLANTER .**

**CEILING -POP CEILING,CEILING LIGHT**

## **SUITE**

- Our Suite are contemporary and elegant with a separate living room and guest bathroom. The living room opens into a private balcony. Daily newspaper, mini bar (on charge), tea/coffee maker, LCD TV in both rooms, iron & ironing board, hair dryer, in room safe, complimentary Wifi access.
- Room features
- Air conditionned room



**SUITE INTERIOR VIEW**

## **MATERIALS USED GUEST ROOM**

**FLOORING – TILE – WOODEN PLANKS**

**WALL- PAINTS AND WALLPAPER**

**CEILING- POP CEILING, CEILING LIGHT SIDE TABLE LAMP**

**SANITARY FITTINGS- TOTO COMPANY**

**FURNITURE- PLY BOARD, WOODEN LAMINATES , WHITE LAMINATES**

**WINDOWS- FIX GLASS WITH CURTAINS**


**DOORS- DESIGNER PLY WOOD DOOR WATERPROOF**

## **SUPERIOR ROOM**

- Functional accommodation, Daily newspaper, mini bar (on charge), daily newspaper, tea/coffee maker, LCD TV, hair dryer, in-room safe, complimentary Wifi access.

### **Room features**

- Air conditionned room
- Area :-248 sq.ft.
- Double Bed sized bed
- Superior room is in HERITAGE WING. Functional accommodation, Daily newspaper, mini bar (on charge), daily newspaper, tea/coffee maker, LCD TV, Hair Dryer, in room safe, complimentary Wi-Fi access



**SUPERIOR ROOM INTERIOR VIEW**

## **CLUB ROOM**

- Our Club rooms are contemporary and elegant. Warm & comfortable space offering a great city view. Daily newspaper, mini bar (on charge), tea/coffee maker, LCD TV, iron & ironing board, hair dryer, in-room safe, complimentary Wifi access.

### **Room features**

- Air conditionned room
- Area :- 269 sq.ft.
- King Bed sized bed
- Club Rooms in NEW WING Contemporary elegance and style best describe our Club rooms. Warm and comfortable space offers a great city view with complimentary breakfast. Additional amenities include high speed Wi-Fi connectivity, a work station, LCD TV and direct dial phone. Additional facilities include a small fruit platter, assorted chocolates, tea/coffee maker with choice of tea, coffee, sugar (brown, white and sugar-free), daily newspaper, in-room safe, iron and ironing board, bottled water and a well stocked mini bar



**CLUB ROOM INTERIOR VIEW**

## **DELUXE ROOM**

- Spacious accommodation, daily newspaper, mini bar (on charge), tea/coffee maker, LCD TV, hair dryer, in-room safe, complimentary Wifi access.




### **Room features**

- Air conditionned room
- Area :-301 sq.ft.
- Double Bed sized bed



**DELUXE ROOM INTERIOR VIEW**

## ALL DAY DINING(BRANCHE RESTAURANT)



**RESTAURANT INTERIOR VIEW**



## **MATERIALS**

**FLOORING – TILE – WOODEN PLANKS**

**WALL- PAINTS AND WALLPAPER WITH WOODEN ACP ,DESIGNER GLASS**

**CEILING- POP CEILING ,PLASTIC SHEET,CEILING LIGHT ,COVE LIGHT,ACP SHEET**

**SANITARY FITTINGS- TOTO COMPANY**

**FURNITURE- PLY BOARD, WOODEN LAMINATES , STAINLESS STEEL ,FOAM AND LINEN FABRIC**

**WINDOWS- FIX GLASS WITH CURTAINS**

**DOORS- DESIGNER PLY WOOD DOOR WATERPROOF**

# **CHAPTER-05**

## **CONCEPT**

## **THEME (BIOPHILIC THEME)**

### **BIOPHILIC DESIGN**

Biophilic design is the increasing trend of designing places for people to feel physically and psychologically comfortable. To achieve biophilic design, it's important to take into consideration the natural environment that surrounds us, as well as the human body. Furniture should be made with sustainable materials like walnut, bamboo, and cedar. Colors should be chosen based on what Mother Nature provides – greens, browns, blues, etc.

## **HISTORY**

### **Founder of Biophilic Design**

E.O. Wilson in his 1984 book *Biophilia*.

### **God father of Biophilic design**

Godfather of *Biophilia* Dr Stephen Kellert's .

### **Father of Green Architecture**

Frank Lloyd Wright.

## **BACKGROUND RESEARCH**

### **1980s**

BIOPHILIC DESIGN COINED AS A DESIGN STRATEGY BY STEPHEN KELLERT.

### **2006**

LIVING BUILDING CHALLENGE DEVELOPED BY ILFI , THE FIRST RATINGS SYSTEM TO INCLUDE BIOPHILIA.

### **2008**

STEPHENE KELLERT'S FIRST FRAMEWORK FOR BIOPHILIC DESIGN PUBLISHED IN BIOPHILIC DESIGN.THE THEORY,SCIENCE,AND PRACTICE OF BRINGING BUILDING BUILDING TO LIFE.

## 2014

ILFI PUBLISHES BOOK CREATING BIOPHILIC BUILDING. TERRAPIN BRIGHT GREEN DEFINES A NEW FRAMEWORK FOR BIOPHILIC DESIGN. FOURTEEN PATTERNS OF BIOPHILIC DESIGN.


## 2018

STEPHEN KELLERT'S CONSOLIDATED FRAMEWORK FOR BIOPHILIC DESIGN PUBLISHED IN NATURE BY DESIGN. THE PRACTICE OF BIOPHILIC DESIGN.

## 2020

BIOPHILIC DESIGN GUIDE BOOK PUBLISHED BY WILLIAM BROWNING AND CATHERINE ORYAN, NATURE INSIDE.

## CONCEPT



- Site Have A South Facing Orientation, And Building having the L Shape Constrction . South Is The Hottest Direction So We Take The Higher Setback And A Front Courtyard For Landscaping And Water Body For Reduce The Temparature, South Facing Windows Receive Minimal Sun And Should Be Relatively Small To Minimise Heat Loss But Allow For Diffused Or Reflected Light And Ventilation.
- In West Direction We Have A Sufficient Space Having A Lot Of Trees And Landscaping So They Release Fresh Air And Make Temparatre So Cool .
- In North We Take More Glazing, Openings And Balconies Because North Having A Cool Temprature And Have A Good Natural Daylight.
- In East We Have Openings And Windows So Because East Facing Glazing Captures Morning Sun And Can Be Sized According To Your Preference In Smmer For Light, Heat , Control And Ventilation.

## **BENEFITS OF BIOPILIC DESIGN IN HOTEL**

- Stress levels begin to decline as the brain relaeses dopamine that feel good hormone that lifts the spirits Research shows that exposure to green spaces and bioplilic features is the perfect antidote to our urban lifestyle.
- This positive reaction to natural surrooundings is the goIJJial of successful biophilic design hotels around the world. An abundance of sunlight views of open air landscapes vertical gardens,scattered vegetation , and other types of biophilic decor. help hotels resorts and restaurants create a memorable experience.
- Hotel rooms with an ocean or water view are priced up to 20 percent higher.
- Customers rate biophilic designs hotels in terms of wellness relaxation and sleep quality.
- The first and one of our personal favorite design innovations for hotels is live edge furniture. Live edge furniture can be made from a variety of wood types, but the most common are hardwoods such as cherry, maple, and oak.
- Wall Gardens:A Hotel's Best Friend. Nature is practically relegated to our backyards, hotels have been looking for new ways to make their spaces feel more fresh and inviting.Hotel rooms are usually small and densely used.Guests will still enjoy the benefits of greenery without sacrificing

precious room space. Wall Garden also provide a wide range of benefits for the environment and the people who live there. The plants help to control indoor air pollution .


- The Global Impact of Biophilic Design in the Workplace”, a 2021 study from Human Spaces, found that workers in offices with natural elements, such as greenery and sunlight achieve: 6% more productivity , 15% more creativity , 15% higher levels of well-being.Biophilic design connecting people with the natural environments.Guest are willing pay more for Biophilic designed Rooms.
- The benefits of biophilic design for interior for interior spaces are firmly based in science. Humans have an innate affinity for nature and elements that echo the patterns sound and colors of the outdoors. viewing a spring garden a burbling fountain or verdant wallscape planters the physical and emotional impact is the same.

### **EXAMPLE OF BIOPHILIC DESIGN**





**RESIDENCE :-FALLING WATER BY FRANK LLOYD WRIGHT (ORGANIC ARCHITECTURE)**



**BIOPHILIC HOTEL PARKROYAL (SINGAPORE)**

## BIOPHILIC DESIGN PRINCIPLE



## BIOPHILIC DESIGN PRINCIPLE



DECOR



AIR QUALITY




SOUND



MATERIALS



LIGHT



NATURAL LIGHT



SHAPE FURNITURE



GREENERY



USE NATURAL COLOUR

## **BIOPHILIC DESIGN ELEMENT**

### **ENVIRONMENTAL FEATURES**

WATER, AIR, SUNLIGHT, COLOR, PLANTS, ANIMALS, NATURAL VIEWS ,FIRE, ECOSYSTEM.



### **NATURAL SHAPES AND FORMS**

BOTANICAL MOTIFS, TREE AND COLUMNAR SUPPORTS SHELLS AND SPIRALS, ANIMAL MOTIFS, BIOMIMICRY OVAL SHAPES, ARCHES, VAULTS DOMES, SHAPES RESISTING STRAIGHT LINES AND RIGHT ANGLES.



### **NATURAL PATTERNS AND PROCESSES**

DESIGNING WITH CULTURAL SPIRITUAL,  
ECOLOGICAL, OR HISTORICAL RELATIONSHIPS IN  
MIND.



### **LIGHT AND SPACE**

NATURAL LIGHT FILTERED AND DIFFUSED LIGHT  
LIGHT AND SHADOW LIGHT POOLS, SPATIAL VARIETY  
SPATIAL HARMONY SPACIOUSNESS, INSIDE OUTSIDE  
SPACES.



### **PLACE-BASED RELATIONSHIPS**

GEOGRAPHIC CONNECTION TO PLACE, ECOLOGICAL  
CONNECTION TO PLACE, CULTURAL CONNECTION TO  
PLACE INDIGENOUS MATERIAL, LANDSCAPE  
ORIENTATION, LANDSCAPE ECOLOGIC AVOIDING  
PLACELESSNESS.



## EVOLVED HUMAN-NATURE RELATIONSHIPS

DESIGNING TO MAINTAIN  
STRONG REACTIONS/CONNECTIONS TO OUR  
PROTECTION MASTERY AND CONTROL,  
EXPLORATION AND DISCOVERY.



## MATERIALS USED IN BIOPHILIC DESIGN

### FLOORING

- Flooring has always been at the vanguard of biophilic design. From wood, natural stone and marble floors to wool, sisal and coir carpets, floors have traditionally been constructed from natural materials.



### FURNITURE

- Wood(hardeoood )cherry,maple and oak)
- Cork,Bamboo,Linen,Rattan,Stone.



## **WALL FINISHES**

**WALLPAPER/WAL MURALS:**-Simple choice for indirect contact with nature are murals and wallpapers, provided that they integrate well with the rest of your space and the surrounding environment as specified in the beginning.



**MOSS:**-Preserved moss is a great way to introduce a low-maintenance green wall in an interior. Make sure to choose one that has not a flat bright green colour, available leaves and varied textures. They don't need water.

**STONE,WOOD,PATTERN(FLORA AND FAUNA) PAINT,TEXTURE,WALL HUNG PLANTER,WLL MOUNTED SHELEVES,SPARSE GARDEN WALL,TERRACOTTA.**



## LIGHTING

CEILING LIGHT, PROFILE LIGHT, COVE LIGHT, WALLS CONES, HANGING PENDANT.




## PLANTER



## BIOPHILIC DESIGN IN 5 STAR HOTEL





## MOOD BOARD



NATURAL COLOUR PALLETE



## BIOPHILIC PLANTS



GOLDEN POTHO



ZZ PLANT



CORN PLANT



UMBRELLA TREE



GARDENIA CARE



WARNECK DRACAENA



SNAKE PLANT



CHOCOLATE MINT

## FLOORING FINISHES



## BIOPHILIC MATERIALS



LINEN




## CORK



## WOOD




## BAMBOO




## LIGHTING


## **BIOPHILIC DESIGN IN RECEPTION WAITING AND COFFEE SHOP**




**WAITING AREA**




**DÉCOR PLANTER**




**PLANTER**



**SIMPLE CEILING WITH HEAVY CHANDELIER**



RECEPTION



SIMPLE CEILING WITH HEAVY CHANGLIER



CARPET

FLASE CEILING




FLOORING




LORD BUDDHA WITH TREE



STAIR DESIGN WITH GREENERY



WALL FOUNTAIN



STAIR WALL DESIGN



HANGING GRASS



PLANTER



## MODERN THEME IN HOTEL ROOM




**WARDROBE**



**SLIDER**



**GLAZING WITH CURTAIN**



**PRESIDENTIAL SUITS**



DÉCOR. LAMP



DRAWING HALL TV UNIT



WALL PANELLING



DRESS AREA




TV UNIT



KITCHEN DESIGN



BATH AREA



FLOOR LAMP




BED BACK DESIGN



DINNING SPACE

## MODERN THEME IN HOTEL ROOM



**SINGLE ROOM FURNITURE LAYOUT**  
**4255 X 6915**



**WOODEN PANELLING**



**FLOOR LAMP**



**PLANTER**



**WARDROBE**




**CEILING LIGHT**



**DRESSING CHAIR**



**WINDOW AND  
CURTAIN DESIGN**






**WARDROBE**



**FLOORING**

**SINGLE ROOM**



**CEILING**




**CEILING**



**PLANTER**



**CHAIR**



**DRESSING MIRROR**



**FLOOR LAMP**

**DOUBLE ROOM**


# **CHAPTER-06**

## **5 STAR HOTEL STANDARDS**


## 5 STAR HOTEL STANDARD

### GUEST ROOMS LAYOUT

- Floor to ceiling heights are usually 2.3 - 2.5m.
- Most critical plan dimension is room width: 3.6 m(12ft) is efficient.
- Corridor space should be about 6m sq per room, with minimum width of 1.5 - 1.8 m.





**NARROW FRONTAGE:**  
**MIN.WIDTH 3M.**



**DOUBLE BED**



### GUEST BATHROOMS

- Bathrooms are mainly sited in the interior walls."Adjacent pairs of rooms are arranged mirror image to share common vertical ducts.
- Typical fittings: for high grade hotel 1700mm bath, twin basins, wc, separate dressing area and shower.




### GUEST - FLOOR SERVICE SPACE

- It is the place where the linen is stored and where maids' carts are kept.
- Each maid will handle anywhere from 12 to 15 rooms with a cart.
- A close storage area should be provided for storing of linen. and specially for carts.**WITH SEPARATE**
- Storage for toilet facilities are also provided.



## FLOOR LAYOUT:

- Organize plan so that guest rooms occupy atleast 70% of GROSS FLOOR AREA.
- Locate elevators and stairs at interior locations rather than exterior walls.
- Develop corridor plan to facilitate guest circulation.
- Linen storage and duties in central location.
- Plan corridor width at 1.5 m (minimum). to 1.6 m (minimum).
- Plan guest room distance to exist stairs at 150 exist stairs at 150' (30m) maximum."Design guest rooms back to back for planning economics.




## ELEMENTS FOR COMPLETE GUEST ROOM DESIGN

- Case pieces - Desk, dresser, tables"
- Soft goods -Bedspreads, upholsteries.
- Lighting Lamp at beside desk
- Accessories - Mirrors, art, planters.

## GUESTROOM FINISHES:

- Floor -Generally carpeted
- Wall - Vinyl wall covering or paint
- Ceiling -Acoustical treatment"Doors -Wood, pre-finished



## BATHROOM FINISHES:


- Floor -Ceramic Tiled
- Walls Ceramic or marble tile.

## ACOUSTICS

- Guest rooms wall should be designed so that it does not transfer sound from one room to another


## MECHANICAL / ELECTRICAL

- Cable - TV, Telephone, Fire Alarm, Other communication Systems.
- Mechanical -HVAC integrated with room layout bathroom exhaust.
- Fire protection One smoke detector and sprinkler, furnishings of fire retardant capacity.



## GUEST BATHROOMS

- The bathroom of the 5 x 8 ft. dimensions is still used today and accommodates comfortably the standard three fixtures.
- But competitive pressure, and marketing, and guests' eagerness for something better than they have at home, has pushed the first-class and luxury operators to add fixtures and





### **GUESTROOM AND SUITE DESIGN (MIN. DIMENSIONS)**

	LIVING AREA		BATHROOM		TOTAL GUESTROOM	
	DIMENSIONS (FT)	AREA (SQ.FT.)	DIMENSIONS (FT)	AREA (SQ.FT.)	DIMENSIONS (FT)	AREA (SQ.FT.)
BUDGET	11.5 x 15	172	5 x 5	25	11.5 x 20.5	236
MID-PRICE	12 x 18	216	5 x 7.5	37	12 x 26	312
UPSCALE	13.5 x 19	256	5.5 x 8.5	47	13.5 x 28.5	378
LUXURY	15 x 20	300	7.5 x 9	71	15 x 30	450

Notes: 1. Living area does not include the bathroom, closet or entry.  
 2. Budget guestroom bath includes tub/shower and toilet but the washbasin is part of the dressing area.  
 3. Dimensions & Layout of rooms depend upon the size and Nos. of Beds:

	LIVING AREA		BATHROOM		TOTAL GUESTROOM	
	Dimensions (ft)	Area (sq.ft.)	Dimensions (ft)	Area (sq.ft.)	Dimensions (ft)	Area (sq.ft.)
BUDGET	11.5 x 15	172	5 x 5	25	11.5 x 20.5	236
MID-PRICE	12 x 18	216	5 x 7.5	37	12 x 26	312
UPSCALE	13.5 x 19	256	5.5 x 8.5	47	13.5 x 28.5	378
LUXURY	15 x 20	300	7.5 x 9	71	15 x 30	450



#### FITNESS FACILITIES CHECKLIST

HOTEL TYPE	NO. OF SPACES/R OOM	COMMENT
Boutique hotel	0.3-0.8	High factor in resort areas
Suburban hotel	1.2-1.4	Heavy local meeting and banquet use
Airport hotel	0.6-1.0	Moderate retail car use
Resort (all types)	0.2-1.4	Varies by market, location, and proximity to urban centers or major attractions
All-suit hotel	0.8-1.2	Limited F&B and function areas
Luxury hotel	1.0-1.2	Limited function areas
Mixed-use hotel	0.6-1.2	Highly variable depending on other activities
Casino hotel	0.8-2.0	Varies by location

AREAS	%AGE	AREA PER PERSON(SQMTS)
FOR DINING AND COFEE SHOP	60	0.9-1
FOR COFEE SHOP ONLY	40	0.6
FOR BANQUET	8	0.24
FOOD, LIQUOR, CHINA STORAGE	50	0.5

## **KITCHENS**

- The size of the kitchen required is determined by the number of workstations, the space required for equipment, the range of meals and extent of food preparation.
- It can service coffee shop, banquet hall, conference halls ,and room service. In this case the kitchen should be 33percent more than the main dining space.AREA REQUIREMENTS KITCHENS.FOR DIFFEREN

## **PLANNING OBJECTIVES**

- Straight line flow of food from storage-serving.
- Eliminate cross-traffic and backtracking.
- Minimize distance between kitchen serving area and restaurant seating.

## **KITCHEN SUPPORT AREAS**

Place chief's office with room service area and garde-manger area close to cooking.

### **EMPLOYEE FOOD SERVICE**

- Entry from service corridor.
- Provide minimum distance from kitchen serving area and restaurant seating.
- Locate secondary storage near each station.

### **PROGRAM:**

- 6sq ft (0.6 sq m)/ restaurant seat.
- 2 sq ft (0.2 sq m) / banquet seat.
- 1 sq ft (0.1 sq m) /lounge seat.
- 1 sq ft (0.1 sq m) /hotel guestroom.
- 30 -50% of main kitchen area is for foodand Beverage storage.

### **FOOD- SERVICE ADJACENCIES ESSENTIAL:**

- Food storage main kitchen.
- Main kitchen to restaurant.
- Room service area to service elevators.
- Banquet pantry to ballroom.
- Desirable: Receiving to food storage.
- Main kitchen to banquet pantry.
- Banquet pantry to smaller banquet rooms andPre functional area.
- Coffee shop pantry to room service area.
- Kitchen to cocktail lounge, garbage/trash holding.
- And employee dining.

## **5 STAR HOTEL STANDARD**

### **HOTEL AREAS DEFINED**

S.NO	PUBLIC AREAS	PRIVATE AREAS(STAFF)	PRIVATE AREAS(GUEST)	SEMI PRIVATE
1	LOBBY + RECEPTION	ADMINISTRATION OFFICE	SINGLE BEDROOM	BANQUET
2	RESTAURANTS	ACCOUNTS OFFICE	DOUBLE BEDROOM	DINING HALL
3	SHOPS + RETAIL STORE	TECHNICAL/MECHANICAL ROOMS	DELUXE BEDROOM	MULTIPURPOSE HALL
4	LOUNGE + BAR	BEDROOMS	SUITE BEDROOM	
5	CLOAK ROOM	LAUNDRY + STORAGE	STEAM ROOMS + SPA	
6	PARKING	KITCHEN + STORAGE	LOUNGE + BAR	
7	RECREATIONAL AREAS(OUTDOOR)	CONTROL ROOM	READING	
8	BANQUET	WASTE DISPOSAL	RECREATIONAL AREAS (SWIMMING POOL, PARKS)	
9		LOCKERS + WASHROOMS		
10		PANTRY		

### **BUILDING BYE LAWS•**

#### **THERE ARE TWO MAIN AREA IN A HOTEL:**

1. FRONT OF THE HOUSE - The greeting area, is known as the front of the house. Main areas are lobbies, dining spaces, rest rooms, passenger elevators, corridors, hotel rooms, etc
2. BACK OF THE HOUSE- where the guests service amenities were taken care of Main functions are laundering foodstuffs, housekeeping supplies, and many other services that must be kept out of sight of the hotel guests.

#### **BUILDING BYE LAWS AREA REQUIREMENT**

for corridors

1. Corridor space should be about 6msq per room
2. At least 1.5 to 1.80 m wide
3. Separate routes should be provided for guests, staff and goods.

## **HOTEL (5 STAR)**

- It must have a minimum plot size of 5000 sq. mt.
- F.A.R is allowed upto 3 (20-25% of this FAR can be used for commercial purposes)
- Ground coverage upto 40%
- Parking -1 ECS per 100 sq. mt. of covered area

## **ACCESSIBILITY AND CIRCULATION**

- Segregation of the vehicular and the pedestrian route.
- Access to the service areas (load, trash and employee entrance) for max. efficiency while avoiding cross circulation or inconvenience to the guests.


## **VIEW**

Guest rooms view often are crucial and are captured

by:

- Orientation of the building.
- Developing the built form. In case of a low-rise profile or absence of 360deg. Natural view, it is mandatory to:
- Create interesting features or treat the terrain in different ways.
- Designing small gardens or pleasant landscape vistas.
- Directing views across swimming pools or in to interior atriums. In case of special view of mountains or the
- The guestrooms maybe constructed as a singly-loaded corridor building with rooms.

FUNCTIONS	%AGE
ACCOMODATION INCLUDES ROOMS , BATHROOMS , SHOWER ROOMS ETC.	60-70
PUBLIC GUEST ROOMS , A RECEPTION AREA, HALL AND LOUNGES ,	4-7
HOSPITALITY AREA, RESTAURANTS , BARS FOR THE VISITORS AND GUESTS.	4-8
BANQUETING AREA WITH MEETING ROOMS AND CONFERENCE NEEDS.	4-12
DOMESTIC AREAS , KITCHENS, PERSONAL ROOMS AND STORES.	9-14
ADM. MANAGEMENT AND SECRETARIAL.	1-2
MAINTENANCE AND REPAIR.	4-7
LEISURE , SPORTS , SHOPS , SALON.	2-10




## DEVELOPING THE SITE AND THE MASTER PLAN FOR THE HOTEL




establishing the concept for the site it is critical to prioritize the programs and goals:

- The views from the public spaces and the guestrooms.
- Alternate amenities for different guest segments, say families or business travelers.
- Conserving a portion of the site for the future

**ADMINISTRATION OFFICES**



	in	cm
A	40-48	101.6-121.9
B	24 min.	61.0 min.
C	18	45.7
D	22-30	55.9-76.2
E	78 min.	198.1 min.
F	24-27	61.0-68.6
G	36-39	91.4-99.1
H	8-9	20.3-22.9
I	2-4	5.1-10.2
J	4	10.2
K	44-48	111.8-121.9
L	34 min.	86.4 min.
M	44-48	111.8-121.9
N	54	137.2
O	26-30	66.0-76.2
P	24	61.0
Q	30	76.2
R	15-18	38.1-45.7
S	29-30	73.7-76.2
T	10-12	25.4-30.5
U	6-9	15.2-22.9
V	39-42	99.1-106.7





## **DINING ROOM, BUFFET, BARS, COFFEE SHOPS, BREAKFAST ROOM**

- Recommended areas are:
- Dining rooms (luxury): 1.7 m sq - 1.9 m sq. per seat.
- Coffee shops and standard restaurants: 1.3 m sq per seat.
- Dances floor should not be less than 6.3 m wide in direction.



## **RESTAURANTS**

- Typical areas for high class restaurant: 2.0 - 2.4 m sq per seat" Service areas
- Main kitchen- Banquet kitchen Satellite service kitchen 15.500.72.0.60-1
- Furniture stores (ballroom):" Structural columns in a dining room are best in the middle of a group of tables or at a corner of a table. servery\* Window area should be greater than equal to 1/10 of the room area of the restaurant.
- The min. width of the escape routes is 1.0 m per 150 people.msq/ cover 0.9-1.0 0.2 - 0.3 0.3 - 0.4 0.2





## EATING SPACE

TYPICAL SIZES AND SHAPES OF DINING TABLES			
TYPE	SHAPE	MINIMUM SIZE (IN.)	SPACIOUS (IN.)
TABLES FOR 1'S OR 2'S	SQUARE	24 X 24	30 X 30
	RECTANGLE	24 X 30	30 X 36
	ROUND	30	36
TABLES FOR 3'S OR 4'S	SQUARE	30 X 30	42 X 42
	RECTANGLE	30 X 42	36 X 48
	ROUND	36	48
TABLES FOR 5'S OR 6'S	RECTANGLE	30 X 60	42 X 72
ROUND			






AREA OF MODULE 5.35SQ.M.

AREA PER SEAT 1.34SQ.M



AREA OF MODULE 4.61SQ.M.

AREA PER SEAT 1.15SQ.M.






AREA OF MODULE 3.61 SQ.M.

AREA PER SEAT .90 SQ.M.

## WALL TABLES

## DIMENSIONS OF TABLE





## CONFERENCE ROOMS

CONFERENCE ROOM FOR 25 PERSONS	
Size Of Room	5.3 m. x 11.5 m.
Area Per Person	2.4 sq.m.

## FUNCTION ROOM CHARACTERISTICS

SPACE AND USES	PRINCIPAL PLANNING REQUIREMENTS	CAPACITY FOR HOTEL TYPES
Ballroom Meetings, banquets, receptions, exhibits	Divisibility, high ceiling, direct food access, no columns	2 x GR
Ballroom foyer Reception, registration, flow meeting	Access to all ballroom sections and support, functions access to terraces	.2 x BR
Banquet rooms Banquets, receptions meetings,	Divisibility, direct food access, natural light	.2-.6 x BR
Meeting rooms Meetings, limited banquets	Built-in-audiovisual, limited divisions	.2-.4 x BR
Board room High level meeting	Separate from other meeting rooms, built-in audiovisual, superior finishes	12-20 people


# **CHAPTER-07**

## **BIBLIOGRAPHY**


- <https://www.slideshare.net/joshikaagrawal/lucknow>
- <https://www.slideshare.net/Abhinavmaurya23/lucknow-tourism-54150530>
- <https://www.canarytechnologies.com/post/types-of-rooms-in-5-star-hotels#:~:text=A%20deluxe%20room%20is%20one,group%20or%20for%20small%20families>
- <https://en.climate-data.org/asia/india/uttar-pradesh/lucknow-2850/>
- <http://www.se-arch.com/studio.php>
- <http://vivanta-by-taj-whitefield.hotels-in-bangalore.com/en/>
- <https://www.re-thinkingthefuture.com/interior-design/a8272-10-examples-of-biophilic-interior-design/>
- <https://thestoryboxx.com/blogs/article/how-biophilic-design-has-influenced-the-hospitality-industry>
- <https://www.habitarmonia.com/how-to-use-color-with-biophilic-design>
- <https://www.planteriagroup.com/blog/the-three-pillars-of-biophilic-design/>
- <https://www.slideshare.net/NamrathaBs/hotel-avasa>.
- <https://www.booking.com/hotel/in/avasa.html>
- <https://www.vivantahotels.com/en-in/vivanta-bengaluru-whitefield/>
- <https://www.booking.com/hotel/in/vivanta-by-taj-whitefield-bengaluru.htm>
- <https://www.hotelavasa.com>
- <https://www.scribd.com/document/463888545>
- <https://www.scribd.com/document/368769744/Hotel-avasa-CHUMMA-pdf>
- <https://www.scribd.com/presentation/440013867/Avasa-Hotel>
- <https://www.guestreservations.com/golden-tulip-lucknow/booking?msclkid=4325574c435f1faffa5933d0886af535>
- [https://www.tripadvisor.in/Hotel\\_Review-g297684-d1673806-Reviews-Golden\\_Tulip\\_Lucknow-Lucknow\\_District\\_Uttar\\_Pradesh.html](https://www.tripadvisor.in/Hotel_Review-g297684-d1673806-Reviews-Golden_Tulip_Lucknow-Lucknow_District_Uttar_Pradesh.html)
- [https://www.tripadvisor.in/Attractions-g297684-Activities-Lucknow\\_Lucknow\\_District\\_Uttar\\_Pradesh.html](https://www.tripadvisor.in/Attractions-g297684-Activities-Lucknow_Lucknow_District_Uttar_Pradesh.html)
- [https://www.tripadvisor.in/Attractions-g297684-Activities-c47-t163-Lucknow\\_Lucknow\\_District\\_Uttar\\_Pradesh.html](https://www.tripadvisor.in/Attractions-g297684-Activities-c47-t163-Lucknow_Lucknow_District_Uttar_Pradesh.html)

# **CHAPTER-08**

## **DESIGN DEVELOPMENT**



**KEY PLAN**




**SITE PLAN**

**PROJECT :-  
5 STAR HOTEL**


DRG TITLE-		INTERIOR DRAWING
DATE-		25/06/2023
SCALE		
SHEET NO-		
SIGN	REMARK	

DRAWN BY - RAJKANYA SINGH  
**INTERIOR DESIGN THESIS**  
 B.I.D.-IV YEAR, 8TH SEMESTER  
 BABU BANARASI DAS  
 UNIVERSITY, LUCKNOW.U.P


**THESSIS COORDINATOR**  
 AR. VERSHA VERMA  
 AR. SHAILESH KUMAR YADAV  
**THESSIS GUIDE**  
 PROF. KESHAV KUMAR




**SINGLE ROOM FURNITURE LAYOUT**  
4255 X 6915




**SINGLE ROOM FLOORING PLAN**




**SINGLE ROOM  
REFLECTED CEILING PLAN**




**SINGLE ROOM  
ELECTRICAL LAYOUT**



**SINGLE ROOM  
CEILING SECTION X-X'**




**ELEVATION - A**




**ELEVATION - B**



**ELEVATION - C**



**ELEVATION - D**



**WINDOW SIDE RENDERED RENDERED VIEW**

**ELEVATION - A**



**BED BACK WALL RENDERED VIEW**



**TV UNIT RENDERED VIEW**



**SINGLE ROOM**

**PROJECT :-  
5 STAR HOTEL**

DRG TITLE-		INTERIOR DRAWING	
DATE-	25/06/2023		
SCALE			
SHEET NO-			
SIGN	REMARK		

**DRAWN BY - RAJKANYA SINGH  
INTERIOR DESIGN THESIS  
B.I.D.-IV YEAR, 8TH SEMESTER  
BABU BANARASI DAS  
UNIVERSITY, LUCKNOW.U.P**





**THESSIS COORDINATOR**

**AR. VERSHA VERMA  
AR. SHAILESH KUMAR YADAV**






**THESSIS GUIDE**

**PROF. KESHAV KUMAR**

<b>LEGEND</b>		<b>LEGEND</b>	
	FAN		CALL BELL
	CEILING LIGHT		1050
	BULB		2400
	POWER POINT		1800
	POWER POINT (POWER 1.5 AMP FOR TELEPH.)		450
	POWER POINT (POWER 5 AMP FOR T.V.)		450
	POWER POINT (POWER 20 AMP. FOR A.C.)		450
	TELEPHONE		450
	TV		—
	SWITCH BOARD		2550



SYMBOL	DETAIL	HT (MM)	SYMBOL	DETAIL	HT (MM)
	FAN	—		CALL BELL	—
	CEILING LIGHT	—		BELL PUSH	1050
	BULB	1800		EXHAUST	2400
	POWER POINT	450		BED LIGHT	—
	POWER POINT (POWER 5 AMP FOR TELEPH.)	450		MIRROR LIGHT	Mirror ht
	POWER POINT (POWER 5 AMP FOR T.V.)	450		MUSIC SYSTEM	—
	POWER POINT (POWER 20 AMP. FOR A.C.)	450		GOOD NIGHT POINT	450
	TELEPHONE	—		PERSONAL COMPUTER	450
	TV	—		GYSER	—
	SWITCH BOARD	1050		WI-FI	2550



## DOUBLE ROOM

**PROJECT :-**  
**5 STAR HOTEL**

DRG TITLE-		INTERIOR DRAWING
DATE-	25/06/2023	
SCALE		
SHEET NO-		
SIGN	REMARK	











**DRAWN BY - RAJKANYA SINGH**  
**INTERIOR DESIGN THESIS**  
**B.I.D.-IV YEAR, 8TH SEMESTER**  
**BABU BANARASI DAS**  
**UNIVERSITY, LUCKNOW.U.P**

**THEESIS COORDINATOR**

**AR. VERSHA VERMA**  
**AR. SHAILESH KUMAR YADAV**

**THEISIS GUIDE**

**PROF. KESHAV KUMAR**



**PROJECT :-**  
**5 STAR HOTEL**

DRG TITLE-

INTERIOR DRAWING

DATE-

25/06/2023

SCALE

SHEET NO-

SIGN


DRAWN BY - RAJKANYA SINGH  
INTERIOR DESIGN THESIS  
B.I.D.-IV YEAR, 8TH SEMESTER  
BABU BANARASI DAS  
UNIVERSITY, LUCKNOW.U.P

THESSIS COORDINATOR

AR. VERSHA VERMA  
AR. SHAILESH KUMAR YADAV

THESSIS GUIDE

PROF. KESHAV KUMAR



HIGH GLOSSY  
WHITE PORCELAIN TILE  
SIZE-600MM X 600MM  
THICKNESS - 6MM



HIGH GLOSSY  
WHITE PORCELAIN TILE  
SIZE-600MM X 600MM  
THICKNESS - 6MM

HIGH GLOSSY  
MARIN WHITE MARBLE  
1800MM X 1800MM  
THICKNESS - 20 MM

HIGH GLOSSY  
WHITE PORCELAIN TILE  
SIZE-600MM X 600MM  
THICKNESS - 6MM

HIGH GLOSSY  
DARK WOODEN TEXTURE  
CERAMIC TILE  
SIZE-900MM X 900MM  
THICKNESS - 10MM

HIGH GLOSSY  
WHITE PORCELAIN TILE  
SIZE-600MM X 600MM  
THICKNESS - 6MM




LEGEND		
SYMBOL	DETAIL	HT (MM)
◇	CALL BELL	—
○	BELL PUSH	1050
∞	EXHAUST	2400
▷	BED LIGHT	—
—	MIRROR LIGHT	Mirror ht
MS	MUSIC SYSTEM	—
GP	GOOD NIGHT POINT	450
PC	PERSONAL COMPUTER	450
(G)	GYSER	—
■	WI-FI	2550
■	SWITCH BOARD	1050
□	CEILING LIGHT	—
▷	BULB	1800
P15	POWER POINT	450
P5d	POWER POINT (POWER 5 AMP FOR TELEPH.)	450
P5tv	POWER POINT (POWER 5 AMP FOR T.V.)	450
P20	POWER POINT (POWER 20 AMP. FOR A.C.)	450

**PROJECT :-**  
**5 STAR HOTEL**



DRG TITLE- INTERIOR DRAWING	
DATE-	25/06/2023
SCALE	
SHEET NO-	
SIGN	REMARK

DRAWN BY - RAJKANYA SINGH  
INTERIOR DESIGN THESIS  
B.I.D.-IV YEAR, 8TH SEMESTER  
BABU BANARASI DAS  
UNIVERSITY, LUCKNOW.U.P


THESSIS COORDINATOR  
AR. VERSHA VERMA  
AR. SHAILESH KUMAR YADAV  
THESSIS GUIDE  
PROF. KESHAV KUMAR






**PRESIDENTIAL SUITS DRAWING DINNING  
FURNITURE PLAN**



**PRESIDENTIAL SUITS DRAWING DINNING  
HALL REFLECTED CEILING PLAN**



LEGEND		
SYMBOL	DETAIL	HT (MM)
◇	CALL BELL	—
○	BELL PUSH	1050
∞	EXHAUST	2400
□	BED LIGHT	Mirror ht
—	MIRROR LIGHT	Mirror ht
[MS]	MUSIC SYSTEM	—
[GP]	GOOD NIGHT POINT	450
[PC]	PERSONAL COMPUTER	450
(G)	GYSER	—
[Wi-Fi]	WI-FI	2550
■	SWITCH BOARD	1050
□	CEILING LIGHT	—
▷	BULB	1800
[P15]	POWER POINT	450
[PS10]	POWER POINT (POWER 5 AMP FOR TELEPH.)	450
[PS16]	POWER POINT (POWER 5 AMP FOR T.V.)	450
[P20]	POWER POINT (POWER 20 AMP FOR A.C.)	450




**ELEVATION -A**






## PROJECT :- 5 STAR HOTEL

DRG TITLE- INTERIOR DRAWING	
DATE-	25/06/2023
SCALE	
SHEET NO-	
SIGN	REMARK

DRAWN BY - RAJKANYA SINGH  
**INTERIOR DESIGN THESIS**  
B.I.D.-IV YEAR, 8TH SEMESTER  
BABU BANARASI DAS  
UNIVERSITY, LUCKNOW.U.P

THESSIS COORDINATOR  
**AR. VERSHA VERMA**  
**AR. SHAILESH KUMAR YADAV**  
THESSIS GUIDE  
**PROF. KESHAV KUMAR**






## PROJECT :- 5 STAR HOTEL


DRG TITLE- INTERIOR DRAWING	
DATE-	25/06/2023
SCALE	
SHEET NO-	
SIGN	REMARK

DRAWN BY - RAJKANYA SINGH  
INTERIOR DESIGN THESIS  
B.I.D.-IV YEAR, 8TH SEMESTER  
BABU BANARASI DAS  
UNIVERSITY, LUCKNOW.U.P

THESSIS COORDINATOR  
**AR. VERSHA VERMA  
AR. SHAILESH KUMAR YADAV**  
THESSIS GUIDE  
**PROF. KESHAV KUMAR**





**SECTIONAL ELEVATION X - X'**




**PRESIDENTIAL SUITS SINGLE ROOM ELECTRICAL LAYOUT**


SYMBOL	DETAIL	HT (MM)
◊	CALL BELL	—
●	BELL PUSH	1050
∞	EXHAUST	2400
▷	BED LIGHT	—
—	MIRROR LIGHT	Mirror ht
MS	MUSIC SYSTEM	—
GP	GOOD NIGHT POINT	450
PC	PERSONAL COMPUTER	450
(G)	GYSER	—
Wi-Fi	2550	—
■	SWITCH BOARD	1050
□	CEILING LIGHT	—
▷	BULB	1800
P1S	POWER POINT	450
P5U	POWER POINT (POWER 5 AMP FOR TELEPH.)	450
P5T	POWER POINT (POWER 5 AMP FOR T.V.)	450
P20	POWER POINT (POWER 20 AMP. FOR A.C.)	450




**PRESIDENTIAL SUITS SINGLE ROOM FLOORING PLAN**




**PRESIDENTIAL SUITS SINGLE ROOM REFLECTED CEILING PLAN**





**ELEVATION - A**





**ELEVATION - C**



**ELEVATION - B**



**ELEVATION - D**




**PROJECT :-  
5 STAR HOTEL**

DRG TITLE-	
INTERIOR DRAWING	
DATE-	25/06/2023
SCALE	
SHEET NO-	
SIGN	REMARK

**DRAWN BY - RAJKANYA SINGH  
INTERIOR DESIGN THESIS  
B.I.D.-IV YEAR, 8TH SEMESTER  
BABU BANARASI DAS  
UNIVERSITY, LUCKNOW.U.P**

**THESSIS COORDINATOR  
AR. VERSHA VERMA  
AR. SHAILESH KUMAR YADAV  
THESSIS GUIDE  
PROF. KESHAV KUMAR**




## ALL DAY DINING FURNITURE PLAN 387.60 SQ.M.

**PROJECT :-**  
**5 STAR HOTEL**

DRG TITLE-		INTERIOR DRAWING
DATE-	28/06/2023	
SCALE		
SHEET NO-		
SIGN	REMARK	


DRAWN BY - RAJKANYA SINGH  
**INTERIOR DESIGN THESIS**  
B.I.D.-IV YEAR, 8TH SEMESTER  
BABU BANARASI DAS  
UNIVERSITY, LUCKNOW.UP

THESSIS COORDINATOR  
AR. VERSHA VERMA  
AR. SHAILESH KUMAR YADAV  
THESSIS GUIDE  
PROF. KESHAV KUMAR



## ALL DAY DINING FLOORING PLAN


<b>PROJECT :-</b> <b>5 STAR HOTEL</b>	DRG TITLE- INTERIOR DRAWING		<b>DRAWN BY - RAJKANYA SINGH</b> <b>INTERIOR DESIGN THESIS</b> <b>B.I.D.-IV YEAR, 8TH SEMESTER</b> <b>BABU BANARASI DAS</b> <b>UNIVERSITY, LUCKNOW.UP</b>	<b>THESSIS COORDINATOR</b>
	DATE-	28/06/2023		AR. VERSHA VERMA AR. SHAILESH KUMAR YADAV
	SCALE			<b>THESSIS GUIDE</b>
	SHEET NO-			PROF. KESHAV KUMAR
	SIGN	REMARK		



LEGEND		
SYMBOL	DETAIL	HT (MM)
○	FAN	—
□	CEILING LIGHT	
▷	BULB	1800
[P15]	POWER POINT	450
[P5tl]	POWER POINT (POWER 5 AMP FOR TELEPH.)	450
[P5M]	POWER POINT (POWER 5 AMP FOR T.V.)	450
[P20]	POWER POINT (POWER 20 AMP. FOR A.C.)	450
T	TELEPHONE	—
A	TV	—
—	SWITCH BOARD	1050
◁	CALL BELL	—
○	BELL PUSH	1050
∞	EXHAUST	2400
▷	BED LIGHT	—
—	MIRROR LIGHT	Mirror ht
[MS]	MUSIC SYSTEM	—
[GP]	GOOD NIGHT POINT	450
[PC]	PERSONAL COMPUTER	450
(G)	GYSER	—
[FG]	FRIDGE	—
[WM]	WASHING MACHINE	—
[TO]	TOASTER	—
[DW]	DISH WASHER	—
[MW]	MICRO WAVE	—
[MG]	MIXER GRINDER	—
[WP]	WATER PURIFIER	—
[WF]	WI-FI	2550

## ALL DAY DINING REFLECTED CEILING PLAN

<b>PROJECT :-</b> <b>5 STAR HOTEL</b>	DRG TITLE- INTERIOR DRAWING		<b>DRAWN BY - RAJKANYA SINGH</b>  <b>INTERIOR DESIGN THESIS</b> <b>B.I.D.-IV YEAR, 8TH SEMESTER</b> <b>BABU BANARASI DAS</b> <b>UNIVERSITY, LUCKNOW.U.P</b>	<b>THESSIS COORDINATOR</b>  <b>AR. VERSHA VERMA</b> <b>AR. SHAILESH KUMAR YADAV</b>
	DATE-	28/06/2023		
	SCALE			
	SHEET NO-			
	SIGN	REMARK		



### LEGEND

SYMBOL	DETAIL	HT (MM)
	FAN	—
	CEILING LIGHT	—
	BULB	1800
	POWER POINT	450
	POWER POINT (POWER 5 AMP FOR TELEPH.)	450
	POWER POINT (POWER 5 AMP FOR T.V.)	450
	POWER POINT (POWER 20 AMP. FOR A.C.)	450
	TELEPHONE	—
	TV	—
	SWITCH BOARD	1050
	CALL BELL	—
	BELL PUSH	1050
	EXHAUST	2400
	BED LIGHT	—
	MIRROR LIGHT	Mirror ht
	MUSIC SYSTEM	—
	GOOD NIGHT POINT	450
	PERSONAL COMPUTER	450
	GYSER	—
	FRIDGE	—
	WASHING MACHINE	—
	TOASTER	—
	DISH WASHER	—
	MICRO WAVE	—
	MIXER GRINDER	—
	WATER PURIFIER	—
	WI-FI	2550

## ALL DAY DINNING ELECTRICAL LAYOUT

**PROJECT :-  
5 STAR HOTEL**

DRG TITLE- INTERIOR DRAWING	
DATE-	28/06/2023
SCALE	
SHEET NO-	
SIGN	REMARK




DRAWN BY - RAJKANYA SINGH  
INTERIOR DESIGN THESIS  
B.I.D.-IV YEAR, 8TH SEMESTER  
BABU BANARASI DAS  
UNIVERSITY, LUCKNOW.UP

**THESSIS COORDINATOR**

AR. VERSHA VERMA  
AR. SHAILESH KUMAR YADAV

**THESSIS GUIDE**

PROF. KESHAV KUMAR








**PROJECT :-  
5 STAR HOTEL**









DRG TITLE- INTERIOR DRAWING	
DATE-	28/06/2023
SCALE	
SHEET NO-	
SIGN	REMARK

**DRAWN BY - RAJKANYA SINGH  
INTERIOR DESIGN THESIS  
B.I.D.-IV YEAR, 8TH SEMESTER  
BABU BANARASI DAS  
UNIVERSITY, LUCKNOW.UP**

**THESSIS COORDINATOR**  
AR. VERSHA VERMA  
AR. SHAILESH KUMAR YADAV  
**THESSIS GUIDE**  
PROF. KESHAV KUMAR



<b>PROJECT :-</b> <b>5 STAR HOTEL</b>	DRG TITLE- INTERIOR DRAWING		<b>DRAWN BY - RAJKANYA SINGH</b> <b>INTERIOR DESIGN THESIS</b> <b>B.I.D.-IV YEAR, 8TH SEMESTER</b> <b>BABU BANARASI DAS</b> <b>UNIVERSITY, LUCKNOW.UP</b>	<u>THESSIS COORDINATOR</u>
	DATE-	28/06/2023		AR. VERSHA VERMA AR. SHAILESH KUMAR YADAV
	SCALE			
	SHEET NO-			
	SIGN	REMARK		<u>THESSIS GUIDE</u>
				PROF. KESHAV KUMAR



PROJECT :- 5 STAR HOTEL

DRG TITLE-

ICE CREAM KIOSK

DATE-

13/06/2023

SCALE

SHEET NO-

SIGN

REMARK


DRAWN BY - RAJKANYA SINGH  
INTERIOR DESIGN THESIS  
B.I.D.-IV YEAR, 8TH SEMESTER  
BABU BANARASI DAS  
UNIVERSITY, LUCKNOW.U.P

THESSIS COORDINATOR

AR. VARSHA VERMA  
AR. SHAILESH KUMAR YADAV

THESSIS GUIDE

PRO. KESHAV KUMAR





**DECORATIVE ELEMENTS MATERIAL**


1. WOODEN BLOCK WITH ARTIFICIAL PLANTER
2. ARTIFICIAL GREENERY
3. ARTIFICIAL HANGING PLANTS

**STRUCTURAL MATERIAL**


1. BLACK POLISH IRON ROD
2. MILD STEEL FRAMING
3. MILD STEEL JAALI
4. ACP SHEET
5. ACP LOUVERS

**COUNTER AND RACKS MATERIAL SPECIFICATION**

1. 50MM THICK GRANITE COUNTER TOP
2. PLYWOOD , OFF WHITE MICA , SUNMICA , STAINLESS STEEL RACKS AND STAINLESS STEEL HANDLE



**FURNITURE PLAN**



**FURNITURE ELEVATION**

PROJECT :- 5 STAR HOTEL

DRG TITLE-	
ICE CREAM KIOSK	
DATE-	13/06/2023
SCALE	
SHEET NO-	
SIGN	REMARK


DRAWN BY - RAJKANYA SINGH  
INTERIOR DESIGN THESIS  
B.I.D.-IV YEAR, 8TH SEMESTER  
BABU BANARASI DAS  
UNIVERSITY, LUCKNOW.U.P

**THESSIS COORDINATOR**

AR. VARSHA VERMA  
AR. SHAILESH KUMAR YADAV

**THESSIS GUIDE**


PRO. KESHAV KUMAR



**PROJECT :-  
5 STAR HOTEL**

DRG TITLE- INTERIOR DRAWING	
DATE-	28/06/2023
SCALE	
SHEET NO-	
SIGN	REMARK

**DRAWN BY - RAJKANYA SINGH  
INTERIOR DESIGN THESIS  
B.I.D.-IV YEAR, 8TH SEMESTER  
BABU BANARASI DAS  
UNIVERSITY, LUCKNOW.UP**




**THESIS COORDINATOR**


**AR. VERSHA VERMA  
AR. SHAILESH KUMAR YADAV**

**THESIS GUIDE**


**PROF. KESHAV KUMAR**




<b>PROJECT :-</b> <b>5 STAR HOTEL</b>	DRG TITLE- INTERIOR DRAWING		<b>DRAWN BY - RAJKANYA SINGH</b> <b>INTERIOR DESIGN THESIS</b> <b>B.I.D.-IV YEAR, 8TH SEMESTER</b> <b>BABU BANARASI DAS</b> <b>UNIVERSITY, LUCKNOW.U.P</b>	<b>THESSIS COORDINATOR</b>  <b>AR. VERSHA VERMA</b> <b>AR. SHAILESH KUMAR YADAV</b>
	DATE-	28/06/2023		
	SCALE			
	SHEET NO-			
	SIGN	REMARK		




**ELEVATION - A**






**ELEVATION - B**



**ELEVATION - D**



**ELEVATION - C**



## PROJECT :- 5 STAR HOTEL

DRG TITLE-	
INTERIOR DRAWING	
DATE-	28/06/2023
SCALE	
SHEET NO-	
SIGN	REMARK

DRAWN BY - RAJKANYA SINGH  
**INTERIOR DESIGN THESIS**  
 B.I.D.-IV YEAR, 8TH SEMESTER  
 BABU BANARASI DAS  
 UNIVERSITY, LUCKNOW.U.P

### THESIS COORDINATOR

AR. VERSHA VERMA  
 AR. SHAILESH KUMAR YADAV

### THESIS GUIDE

PROF. KESHAV KUMAR

# MATERIAL BOARD

**BRAND:-PHILIP**  
**COLOUR:- WHITE**  
**STYLE :- COOL DAY LIGHT**  
**DIMENSIONS :-160X160X75**  
**DIMENSIONS:- 118X118X19**  
**SHAPE :- CIRCLE, RECTANGLE**  
**MATERIAL :- POLYCARBONATE**  
**WATT :- 12 WATT**  
**PRICE :- 340 / PCS**



## WOODEN TEXTURE PVC SHEET

**MATERIAL :- POLYVINYL CHLORIDE**  
**BRAND :-VI COLLECTIONS**  
**STYLE :-MODERN**  
**SIZE:- 900 X 1800**  
**THICKNESS:- 8 MM**  
**COLOUR:-WOODEN**  
**PRICE :- 790/ ROLL**



## WHITE PROFILE LIGHT

**BRAND :- LEXTON**  
**COLOUR :- WHITE , YELLOW**  
**MATERIAL:-METAL**  
**STYLE:-MODERN**  
**LIGHT FIXTURE FORM :-PATH**  
**APPLICATION AREA:- CEILING, FURNITURE**  
**PRODUCT DIMENSIONS:-30L X 3W X 3H CENTIMETERS**  
**INDOOR/OUTDOOR USAGE :-INDOOR**  
**SPECIAL FEATURE:-ENERGY EFFICIENT**  
**PRICE :- 490 RS / 5 MITTER**  
**WATT :- 12 WATT**



## WOODEN TEXTURE SUNMICASHEET



**SIZE:-2400MMX1200MM**  
**THICKNESS:-1MM**  
**APPL.AREA:-TV UNIT**  
**PRICE:-800/SHEET**  
**BRAND:-CENTURY**  
**SURFACE FINISH:- HIGH GLOSS.**

## BLACK GLASS USED IN CEILING

**SIZE:-1200 MM X 1800 MM**  
**THICKNESS:- 5 MM**  
**APPL.AREA:-CEILING**  
**SIZE :-**  
**BRAND:-SANT.GOBIND**  
**COLOUR:- BLACK**  
**PRICE :- 550 Rs/ SQUARE METTER**



## MOLDED PLASTIC

**SIZE:-LITTER**  
**THICKNESS:-0.8 MM – 1 MM**  
**APPL AREA:-WALL**  
**PRICE:-750RS/ LITTER**  
**BRAND:-ASIAN PAINT**  
**COLOUR:- LIGHT GRAY**

**SIZE:-FREE SIZE**

**THICKNESS:-1 MM – 25 MM**  
**APPL.AREA:- FURNITURE**  
**BRAND:-HONEYWELL**  
**COLOUR:- ANY COLOR**

## ARTIFICIAL GRASS

**SIZE:- 10FT**  
**COLOUR:- GREEN**  
**PRODUCT TYPE :-ARTIFICIAL GRASS**  
**INDOOR/OUTDOOR USAGE :- OUTDOOR, INDOOR**  
**BRAND :-GOASIS LAWN**  
**MATERIAL FEATURE :-NATURAL,POLYPROPYLENE**  
**SPECIAL FEATURE :-WATERPROOF, FADE RESISTANT, NON SLIP,WASHABLE.**  
**EXPECTED PLANT HEIGHT :-20 METRES**  
**PRICE:- 28,000 RS / PCS/ ROLL**  
**SHAPE :- STRAIGHT**



## 10 MM TOUGHENED GLASS

**SIZE:-1200 MM X 2400 MM**  
**THICKNESS:-10MM**  
**APPL.AREA:-DOOR & WALL WITH TABLETOP**  
**PRICE:- 3000 RS / SQUIRE METER**  
**BRAND:-SANT. GOBIMD**  
**COLOUR:- WHITE**




## CLEAR TOUGHENED GLASS

**SIZE:-1200 MM X 1800 MM**  
**THICKNESS:-12MM**  
**APPL.AREA:-GLAZING**  
**PRICE:- 3000 RS / SQ.M.**  
**BRAND:-SANT. GOBIMD**  
**COLOUR:- WHITE**

## WALL PAINT

**COLOUR :- WHITE FOREST**  
**COMPANY:- ULTRATECH**  
**TEXTURE PAINT PVT. LTD.**  
**TEXTURE:- ROUGH**  
**PRICE :- 1000/BAG**  
**APPL. AREA :- WALL**



## WOODEN LOUVERS

**COLOR:-WOODEN TEXTURE**  
**MATERIAL:- PLYWOOD**  
**THICKNESS:-50MM**  
**FINISH:-POLISHED**  
**SIZE:-9.5FT.**  
**SHAPE:-RECTANGULAR**  
**PRICE:-Rs.145/SQ.FT.**  
**BRAND:-MULTIBRAND**




## WALL PAINT

**COLOUR :- WHITE FOREST**  
**COMPANY:- ULTRATECH**  
**TEXTURE PAINT PVT. LTD.**  
**TEXTURE:- ROUGH**  
**PRICE :- 1000/BAG**  
**APPL. AREA :- WALL**

## MARKIN MARBLE

**THICKNESS:-18MM**  
**APPL.AREA:- FLOOR**  
**PRICE:- 480/SQ.FT.**  
**BRAND:- RK MARBLE Pvt. Ltd.**  
**FINISH:- SMOOTH AND GLOSSY.**  
**COLOUR:- WHITE,BLACK.**  
**OTHER NAME:- ITALIAN**  
**WHITE MARBLE**



## GRASS CREEPERS

**MATERIAL:-PLASTIC**  
**COLOUR:-GREEN**  
**SIZE:-SET OF 12 (7.5FT.LONG)**  
**PRICE:-500Rs.**  
**BRAND:-DEEHOME**

## HIGH GLOSSY WHITE PAINT

**SIZE:-LITTER**  
**APPL AREA:-CEILING & WALL**  
**PRICE:-550RS/ LITTER**  
**BRAND:-ASIAN PAINT**  
**COLOUR:- WHITE**

# MATERIAL BOARD

**SIZE:-LITTER**

**THICKNESS:-0.8 MM – 1 MM**

**APPL AREA:-MILD STEEL**

**PRICE:-350RS/ LITTER**

**BRAND:-ASIAN PAINT**

**COLOUR:- BLACK**



## STAINLESS STEEL

**GRADE :- 304**

**THICKNESS:-16 GAZE**

**APPL.AREA:-DOOR**

**AND RAIING**

**PRICE:-280 RS / KG**

**BRAND:-JINDAL**

**COLOUR:- STEEL**



**PLYWOOD**

## FORM USED IN FURNITURE

**SIZE:-1200 X 2400 MM**

**THICKNESS:-50 , 75 ,90 ,110 MM**

**APPL.AREA:-FURNITURE**

**PRICE:-450 RS / KG**

**BRAND:-Dunlop mattress**

**COLOUR:- WHITE**



**SIZE:-1800MMX900MM**  
**THICKNESS:-19MM**  
**APPL.AREA:-CEILING**  
**PRICE:-45-55/SQ.FT.**  
**BRAND:-NATIONAL PLYW**



**KITCHEN FAUCET**  
**MATERIAL:- SS**  
**TYPE:-KITCHEN FAUCET**  
**COLOR:- SILVER**  
**PRICE :- 2799/PIECE**  
**BRAND:- KOHLAR**



## ACP SHEET

**SIZE:-2400MMX1200MM**

**THICKNESS:-3MM**

**APPL.AREA:- CEILING**

**PRICE:-75/AQUARE FT.**

**MATERIAL:- ALUMINIUM**

**COLOUR:- WOODEN**

**BRAND:- EUROBOND**




## TEAK WOOD

**QUALITY :-HEIGHY QUALITY ANTY TERM**

**THICKNESS:-100 MM & 1250MM**

**APPL.AREA:-DOOR FRAME & FURNITUR**

**PRICE:-3500-4000 RS / CUBIC FEET**



## VELVET FABRIC USED IN FURNITURE

**MATERIAL :-VELVET**

**COLOUR:- LIGHT GREY**

**FABRIC TYPE:-VELVET**

**ITEM FORM :-BOLT OF FABRIC**

**BRAND :- SB INDIA**

**PATTERN :-SOLID**

**PRODUCT CARE INSTRUCTIONS**

**MACHINE WASH**

**ITEM DIMENSIONS LXWXH:- 10X**


**10 X 10 CENTIMETERS**

**SPECIAL FEATURE :-ANTIQUE**

**WEAVE TYPE : -VELVET**

**APPL.AREA:- FURNITURE**

**PRISE:- 490 RS / MITTER**



**SIZE:-1200 X 1600 MM**  
**MATERIAL :- VINYL, PAPER,**  
**POLYVINYL CHLORIDE**  
**COLOUR : - AS PER 3D VIEW**  
**BRAND :-DECOR PRODUCTION**  
**STYLE :-MANUAL**  
**ITEM WEIGHT :- 1399 GRAMS**  
**PRISE :- 1050 RS / ROLE**



**I.C.D 55" WIDE**  
**SIZE:-2400MMX1200MM**  
**THICKNESS:-1MM**  
**APPL.AREA:-TV UNIT**  
**PRICE:-950/SHEET**  
**BRAND:-CENTURY**  
**SURFACE FINISH:- HIGH GLOSS.**

## UPVC FRAMING

**THICKNESS:-25-75 MM**

**APPL.AREA:-WINDOW**

**PRICE:-750 RS / RFT.**

**BRAND:- FENEASTA**

**COLOUR:- GLOOSY**



**BLACK GRANITE TOP**

**SIZE:- FREE SIZE**  
**THICKNESS:-25 MM**  
**APPL.AREA:-KITCHEN TOP**  
**PRICE:-160 RS / SQFT**  
**BRAND:-**  
**COLOUR:- HIGH GLOOSY BLACK**

## BRACKET LIGHT

**BRAND :- LYSE DÉCOR**

**COLOUR :- SILVER**

**MATERIAL :-GLASS, METAL**

**STYLE :-MODERN**

**LIGHT FIXTURE FORM :- WALL**

**INDOOR/OUTDOOR USAGE:-INDOOR**

**POWER SOURCE:- ELECTRIC**

**LIGHT SOURCE TYPE :-LED**

**PRICE :- 650 RS / PCS**



## HIGH GLOSSY WALLPAPER

**SIZE:-LITTER**

**APPL AREA:-CEILING & WALL**

**PRICE:-550RS/ LITTER**

**BRAND:-ASIAN PAINT**

**COLOUR:- WHITE**



## BLACK MODERN STOVE

**PRICE:-RS.6999**

**BRAND:-HINDWARE**

**BODY:- TOUGHENED**  
**GLASS**

